

COPY.

H.

Lloyd's Register of Shipping

71, Fenchurch Street, E.C. 3.

enclosure.

20th June, 1923.

Dear Sirs,

With reference to Mr. Kendall's letters of the 11th and 13th instant respecting the oil fuel bunkers proposed to be fitted in the S.S. "WITIAZ", I have to inform you that provided the 4" channel frames be reinforced by $3\frac{1}{2} \times 3\frac{1}{2} \times .40$ " reversed angles at every frame, bracketed both above and below the side stringer, and extending to the underside of the main deck beams and 15" below the top of the tank side brackets, and provided also the oil fuel bunkers be otherwise constructed as shown and amended on the plan forwarded by you to your satisfaction, the requirements of the Rules for burning and carrying oil fuel be complied with so far as applicable, and the flash point of the oil fuel be above 150° F., the proposals will be approved.

It is noted that it is not proposed to proceed with this alteration in the meantime.


A blue print of the plan has been taken and retained in this Office for reference.

I am, Dear Sirs,

Yours faithfully,

Surveyors,

BELFAST.



© 2021

Lloyd's Register
Foundation

Secretary.

W660-0156