

No 884.

S. S. HORAI SAN MARU.

MIDSHIP SECTION.

SCALE 1/2 IN. TO ONE FT.

DIMENSIONS-LENGTH B.P. 407'-3" BREADTH M^{LD} 50'-10" DEPTH M^{LD} 32'-7"

RULE NUMERALS

BREADTH	50.83
DEPTH	32.58
83.41	TRANS. NO.
LENGTH	407.25
33968.72	LONG. NO.
d	19.65
4/0 TO BR. DK.	10.10
4/0 TO UP. DK.	12.50

EQUIPMENT NUMBER

(B+D) x L	(50.83+32.58) x 407.25 = 33,968.72
POOP	3/4 x 39.75 x 7.75 = 231.05
BRIDGE	3/4 x 137.25 x 7.75 = 791.77
F'CLE	3/4 x 45.75 x 7.75 = 265.32
CASCHY CHIMNEY	1/2 x 57.75 x 8.5 = 245.44
DECKHOUSE	1/2 x 23.50 x 8.0 = 94.00
EQUIPMENT NUMBER	35,602.90

EQUIPMENT

TWO BOWER ANCHORS TO BE 20% HEAVIER THAN RULE REQUIREMENTS.

1 BOWER ANCHOR (STOCKLESS TYPE)	76 1/2 CWTs.
1 " " " " " "	76 1/2 " "
1 " " " " " "	54 1/2 " "
1 STREAM ANCHOR (EX. STOCK)	17 1/2 " "
1 KEDGE " " " " " "	7 1/2 " "
270 FATHOMS 2 1/4" DIA. STUO CHAIN CABLE	
90 " 4 3/4" CIR. STEEL STREAM WIRE	
120 " 5" " " WIRE TOW LINE	
2-90 " 2 1/2" " " " HAWSERS	
2-90 " 2 3/4" " " " " "	
90 " 7" " " " " MANILA ROPE WARP LAID	
90 " 7" " " " " " "	
90 " 8" " " " " " CABLE LAID	
90 " 8" " " " " " " "	
2-20 FATHOMS 1 1/4" CIR. SHURO ROPE	



Itoraisan Maru

O.I. Wks. No 884

Midship Section

Rohe Rpt No. 2141

RETAIN



© 2020

Lloyd's Register
Foundation

W667-0030