

23rd October '16.

M.S. "GLENAMOIY".CIRCUITS ON MAIN SWITCHBOARD.

<u>Circuit.</u>	<u>Group.</u>	<u>Cable.</u>	<u>Connected load.</u>
I	Motor Room Lighting.	19/18	36.9
II	Forced Lubricating and Piston Cooling Pumps Port.	19/18	42.
III	- ditto - - ditto - Starbd.	19/18	42.
IV	Circulating Pump.	19/15	86.
V	Sanitary Pump.	19/15	86.
VI	Ballast Pump.	19/15	85.
VII	F.W.Pump, Turning Gear Motor Port & Oil Fuel Pump.	19/16	61.
VIII	Port Bilge Pump and Turning Gear Motor Starbd.	19/16	72.5
IX	Star. Bilge Pump and Workshop Motor.	19/16	66.
X	Searchlight Forward.	19/16	No Search -light ftd before ves -sel left Glasgow.
XI	Spare.		
XII	Spare.		
XIII	Captain, Officers & Navigation Lights.	7/18	15.
XIV	Accommodation Lights.	19/18	54.3
XV	Cargo and Arc Lights.	19/16	58.4
XVI	Wireless.	7/18	20.
XVII	Steering Gear.	19/15	80.
XVIII	Cooking Appliances.	37/13	212.
XIX	Winches Aft.	37/13	798.
XX	" Forward.	37/13	1028.
XXI	Refrigerator Port and Brine Pump Port.	19/14 7/20	101. 33.5
XXII	Refrigerator Starboard and Brine Pump Starboard.	19/14 7/20	101. 33.5


2 Main Dynamos - 3 pairs 91/.098 in parallel each 910 amps output.

1 Tuxham Dynamo

19/15 mains

68

MM.

Gasbath

Ships Register
Foundation