

REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

TUE. 5 AUG. 1924

Received at London Office

Date of writing Report 19 When handed in at Local Office - 1 AUG 1924 Port of SUNDERLAND.

No. in Survey held at SUNDERLAND. Date, First Survey 20th May Last Survey 20th June 1924
Reg. Book. (Number of Visits.....)

on the *Thistleben*

Tons { Gross 4589
Net 2688

Built at *Sunderland* By whom built *Wm Pickersgill & Sons Ltd* Yard No. 210 When built 1924

Owners *Allan Black & Co* Port belonging to *Sunderland*

Electric Light Installation fitted by *Sunderland Forge & Engineering Co Ltd* Contract No. When fitted 1924

System of Distribution *Two Wire*
Pressure of supply for Lighting 100 volts, Heating — volts, Power — volts.

Direct or Alternating Current, Lighting *Direct* Power

If alternating current system, state frequency of periods per second —

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off *Yes*

Generators, do they comply with the requirements regarding overload *Yes*, are they compound wound *Yes*
are they over compounded 5 per cent. *Yes*, if not compound wound state distance between each generator —

Where more than one generator is fitted are they arranged to run in parallel —, is an adjustable regulating resistance fitted in series with each shunt field —

Are all terminals accessible and clearly marked *Yes*, are they so spaced or shielded that they cannot be accidentally earthed, or short circuited *Yes* Are the lubricating arrangements of the generators as per Rule *Yes*

Position of Generators *Engine Room Bottom Platform*
is the ventilation in way of the generators satisfactory *Yes*, are they clear of all inflammable material *Yes*
if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators — and —, are the generators protected from mechanical injury and damage from water, steam or oil *Yes*.

are their axis of rotation fore and aft *Yes*
Earthing, are the bedplates and frames of the generating plant efficiently earthed *Yes* are the prime movers and their respective generators in metallic contact *Yes*

Main Switch Boards, where placed *Close to Generator.*
If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard —

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes *Yes*, are they protected from mechanical injury and damage from water, steam or oil *Yes*, if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards — and —, are they constructed wholly of durable, incombustible non-absorbent materials *Yes*, is all insulation of high dielectric strength and of permanently high insulation resistance *Yes*, if semi-insulating material is used, are all conducting parts connected to one pole insulated from the slab with mica or micanite and the slab similarly insulated from its framework *Yes*, and is the frame effectively earthed *Yes* Are the following fittings as per Rule, viz.:— spacing or shielding of live parts

Yes, accessibility of all parts *Yes*, absence of fuses on back of board *Yes*, proportion of omnibus bars *Yes*, individual fuses to voltmeter, pilot or earth lamp *Yes*, connections of switches *Yes*


Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches *Double Pole Switch & fuses for Generator. Single Pole Switch and Double Pole fuses for Branch circuits.*

Instruments (on main switchboard) 1 ammeters 1 voltmeters — synchronising device for paralleling purposes.

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system *Earth lamps.*

Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules *Yes*

Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule *Yes.*



© 2021

Lloyd's Register Foundation
LW693-0028

Insulation of Cables, state type of cables, single or twin Single 9. Yes are the cables insulated and protected as per Tables III or IV of the Rules Yes

Fall of Pressure, state maximum between bus bars and any point of the installation under maximum load 3 Volts

Cable Sockets and other connections, are the ends of all cables having a sectional area of 0.007 square inch and above provided with soldering sockets Yes.

Paper Insulated Cables. If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound —

Cable Runs, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage Yes

Support and Protection of Cables, state how the cables are supported and protected Armoured & Braided Cable Slipped to Beams

If cables are run in wood casings, are the casings and caps secured by screws —, are the cap screws of brass —, are the cables run in separate grooves —. If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VI Yes

Refrigerated Chambers, if lights are fitted, are the cables and fittings in accordance with the special requirements —

Joints in Cables, state if any, and how made, insulated, and protected None made

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands Yes

Bushes in Beams and Non-watertight Positions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed Yes state the material of which the bushes are made Lead

Earthing Connections, state what earthing connections are fitted and their respective sectional areas —

—, are their connections made as per Rule —

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule Yes

Emergency Supply, state position and method of control of the emergency supply and how the generator is driven none

Navigation Lamps, are these separately wired Yes, controlled by separate switch and separate fuses Yes

are the fuses double pole Yes, are the switches and fuses grouped in a position accessible only to the officers on watch Yes

has each navigation lamp an automatic indicator as per Rule Yes, are separate screens provided for the use of oil and electric side lights Yes

are separate oil lanterns provided for the mast head lights and side lights Yes

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight Yes

are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected —

are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected —

—, how are the cables led —

where are the controlling switches situated —

Searchlight Lamps, No. of —, whether fixed or portable —, are their fittings as per Rule —

Arc Lamps, other than searchlight lamps, No. of —, are their live parts insulated from the frame or case —, are their fittings as per Rule —

Motors, are their working parts readily accessible —, are the coils self-contained and readily removable for replacement —

are the brushes, brush holders, terminals and lubricating arrangements as per Rule —, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material —

are they protected from mechanical injury and damage from water, steam or oil — are their axis of rotation fore and aft —

if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type —, if not of this type, state distance of the combustible material horizontally or vertically above the motors — and —

Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed as per Rule —

Lightning Conductors, where lightning conductors are required, are these fitted as per Rule —

Ships carrying Oil having a Flash Point less than 150° F. Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings —

If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office —

PARTICULARS OF GENERATING PLANT.									
DESCRIPTION OF GENERATOR.	No. of	RATED AT				DRIVEN BY.	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.		
		Kilowatts.	Volts.	Ampères.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.	
MAIN	1	8	100	80	350	Open Type Inverted Steam Engine			
AUXILIARY	—								
EMERGENCY	—								
ROTARY TRANSFORMER	—								

LIGHTING AND HEATING CONDUCTORS.									
Ref. No.	DESCRIPTION.	No. of Conductors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current. Ampères.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	MAIN GENERATOR	2	.06000	19	.064.	80	30	V.I.R.	Lead Covered in Pipe
	AUXILIARY GENERATOR	—							
	EMERGENCY GENERATOR	—							
	ROTARY TRANSFORMER	—							
	AUXILIARY SWITCHBOARDS	—							
	ENGINE ROOM	2	.00701	4	.036	14.4	30	V.I.R.	Lead Covered Armoured & Braided
	BOILER ROOM	—							
	Navigation	2	.00701	7	.036	6.8	300	V.I.R.	Armoured & Braided
	Saloon 9 Forward	2	.01046	7	.044	18.0	280	V.I.R.	Armoured & Braided
	Engineers 9 aft	2	.01046	7	.044	14.8	80	V.I.R.	Armoured & Braided
	WIRELESS	2	.01046	4	.044	16	290	V.I.R.	Armoured & Braided
	SEARCHLIGHT	2	.00194	3	.029	1.2	290	V.I.R.	Armoured & Braided
	MASTHEAD LIGHT MAIN	2	.00194	3	.029	1.2	300	V.I.R.	do do
	SIDE LIGHTS	2	.00194	3	.029	1.2	50	V.I.R.	Lead Covered
	COMPASS LIGHTS	2	.00194	3	.029	.6	20	V.I.R.	Lead Covered
	POOP LIGHTS	—							
	CARGO LIGHTS	2	.00194	3	.029	3.6	250	V.I.R.	Armoured & Braided
	ARC LAMPS	—							
	HEATERS	—							

MOTOR CONDUCTORS.									
Ref. No.	DESCRIPTION.	No. of Motors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current. Ampères.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	BALLAST PUMP								
	MAIN BILGE LINE PUMPS								
	GENERAL SERVICE PUMP								
	EMERGENCY BILGE PUMP								
	SANITARY PUMP								
	CIRC. SEA WATER PUMPS								
	CIRC. FRESH WATER PUMPS								
	AIR COMPRESSOR								
	FRESH WATER PUMP								
	ENGINE TURNING GEAR								
	ENGINE REVERSING GEAR								
	LUBRICATING OIL PUMPS								
	OIL FUEL TRANSFER PUMP								
	WINDLASS								
	WINCHES, FORWARD								
	WINCHES, AFT								
	STEERING GEAR								
	WORKSHOP MOTOR								
	VENTILATING FANS								

