

Chief Ship Surveyor 19. 12. 18

Received from Chief Ship Surveyor

NAME Wood S.S. "WAR QUEBEC".

Rpt. <sup>ml.</sup> ~~ph.~~

No. 1625.

marks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

"The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/02.

urvey

The timbers have been coated with a preservative and the vessel salted as required.

Cwts  
The stockless stream anchor supplied is 10. 0. 0 instead  
Cwts qrs lbs  
of 11. 2. 7 as required.

It is submitted for consideration whether the stockless anchor supplied should be approved.

In other respects the vessel appears worthy to be classed  
\* 12 A1, subject to a Special Survey equal to a Half Time Survey at  
4 & 8 years.


\* 12 A1

1 Dk. 2 tr.Beams. Well Dk.

"Salted".

Lloyd's A & C.P. P & B. 136'. F 30'.


)  
)  
) Subject  
)  
)

  
19. 12. 18

The Surveyor should be informed it is concluded that the beams are 14 x 14 and 12 x 14<sup>6</sup> as shown on the approved plan.

He should also be requested in future cases to give the scantlings of the steel box keelson fitting.

The Surveyor should be requested to state to what special treatment the timbers have been subjected.



© 2021

Lloyd's Register  
Foundation

W734-0009