

COPY.

Lloyd's Register of Shipping.

71, Fenchurch Street, E.C.3.

Enclosure.

21st May, 1937.

Dear Sir,

E. I return herewith one copy of the plan, forwarded with your letter of the 18th instant, of Boiler No.1023 proposed to be constructed by Messrs. David Rowan & Co., Ltd. for Messrs. Lithgows' Yard No.911, and I have to inform you that this plan will be approved for a working pressure of 215 lb. per sq. inch, provided riveted washers the full thickness of the plate be fitted to the lower longitudinal stays at the back end plate, as indicated on the plan, and the boiler be constructed under the usual conditions of survey and testing.

The Steel Testing Surveyors should be advised regarding the tensile strength of the shell plates and butt straps, viz:- 31-35 tons per sq. inch, and of the girder plates, viz:- 29-33 tons per square inch.

I am, Dear Sir,

Yours faithfully,

The Secretary,
GLASGOW.



© 2020

Secretary.

Lloyd's Register
Foundation

W 77-0073