

REPORT ON ELECTRIC LIGHTING INSTALLATION. No. 20162

Port of **New York** Date of First Survey **10 Feb'y** Date of Last Survey **Mar. 11, 1921** of Visits **7**
 No. in Reg. Book on the Iron or Steel **S.S. SAN TIBURCIO** Port belonging to **London**
 Built at **New York** By whom **Standard Shipbdg. Corp.** When built **1921**
 Owners **Eagle Oil Transport Co.** Owners' Address **London**
 Yard No. **29** Electric Light Installation fitted by **Builders** When fitted **1921**

DESCRIPTION OF DYNAMO, ENGINE, ETC.

Two Sunderland Forge Co. 8" x 6" Steam Engine each driving 12½ K.W. Generator.

Capacity of Dynamo **s each 125** Amperes at **100** Volts, whether continuous or alternating current **continuous**
 Where is Dynamo fixed **after engine room** Whether single or double wire system is used **double**
 Position of Main Switch Board **Dynamo Room** having switches to groups **4 Groups** of lights, &c., as below
 Positions of auxiliary switch boards and numbers of switches on each **Upper Engine room, poop deck quarters, midship quarters, forecastle.**

If fuses are fitted on main switch board to the cables of main circuit **Yes** and on each auxiliary switch board to the cables of auxiliary circuits **Yes** and at each position where a cable is branched or reduced in size **Yes** and to each lamp circuit **Yes**
 If cessel is wired on the double wire system are fuses fitted to both flow and return wires or cables of all circuits including lamp circuits
 Are the fuses of non-oxidizable metal **Yes** and constructed to fuse at an excess of **25** per cent over the normal current
 Are all fuses fitted in easily accessible positions **Yes** Are the fuses of standard dimensions **Yes** If wire fuses are used are permanent instructions fitted on or near each switch board giving particulars of proper size of fuse for each circuit **no wire fuses**
 Are all switches and fuses constructed of incombustible materials and fitted on incombustible bases **Yes**

Total number of lights provided for **177** arranged in the following groups:—

Group	Description	Number of Lights	Each of	Candle Power	Requiring a total current of	Amperes
A	lights each of	37	16		45.92	
B	lights each of	40	16		22.40	
C	lights each of	53	16		29.68	
D	lights each of	18	16		10.08	
E	lights each of					
	2 Mast head light with 2 lamps each of	2	16		2.24	Amperes
	2 Side light with 2 lamps each of	2	16		2.24	Amperes
	4 Cargo lights of	4	16			Incandescent

If arc lights, what protection is provided against fire, sparks, &c. **No Arc. Lights**

Where are the switches controlling the masthead and side lights placed **Pilot House Telltale**

DESCRIPTION OF CABLES.

Main cable carrying	161 Amperes, comprised of	2x61 wires, each	.65	B&S S.W.G. diameter, .398	square inches total sectional area
Branch cables carrying	35.92 Amperes, comprised of	7 wires, each	.052	B&S S.W.G. diameter, .0148	square inches total sectional area
Branch cables carrying	22.40 Amperes, comprised of	19 wires, each	.040	B&S S.W.G. diameter, .0237	square inches total sectional area
Leads to lamps carrying	1.12 Amperes, comprised of	1 wires, each	.051	B&S S.W.G. diameter, .0020	square inches total sectional area
Cargo light cables carrying	13.44 Amperes, comprised of	1 wires, each	.064	B&S S.W.G. diameter, .0032	square inches total sectional area

DESCRIPTION OF INSULATION, PROTECTION, ETC.

The Cables are insulated their entire length with a para rubber compound properly applied and vulcanized. Covered with one woven cotton braid and 5/64" lead sheath after which three more woven cotton braids and basket weave navy standard steel armor.

Joints in cables, how made, insulated, and protected **Joints all pigtailed, soldered, rubber and friction taped**
No joints except in brass or galv. iron junction boxes or fixture blocks.

Are all the joints of cables thoroughly soldered, and the flux used not containing acids or other corrosive substances **Yes** Are all joints in accessible positions, none being made in bunkers, cargo spaces, or spaces which may at any time be used for carrying cargo, stores, or baggage **Yes**

Are there any joints in or branches from the cable leading from dynamo to main switch board **No.**

How are the cables led through the ship, and how protected **Lead and Steel Armored navy Standard.**



© 2020

Lloyd's Register Foundation

1177-0110

DESCRIPTION OF INSULATION, PROTECTION, ETC.—continued.

Are they in places always accessible **Yes**

What special protection has been provided for the cables in open alleyways or where exposed to weather or moisture **Lead and steel Armored**

What special protection has been provided for the cables near galleys or oil lamps or other sources of heat **Lead and steel armored**

What special protection has been provided for the cables near boiler casings **Lead and steel armored**

What special protection has been provided for the cables in engine room **Lead and steel armored**

How are cables carried through beams **Holes in beams Lead Sleeved** through bulkheads, &c. **Stuffing Tubes**

How are cables carried through decks **Kick Pipes and stuffing Tubes**

Are any cables run through coal bunkers **No** or cargo spaces **Yes** or spaces which may be used for carrying cargo, stores, or baggage **Yes**

If so, how are they protected **Lead and steel Armored**

Are any lamps fitted in coal bunkers or spaces which may at times be used for cargo, coals, or baggage **No.**

If so, how are the lamp fittings and cable terminals specially protected

Where are the main switches and fuses for these lights fitted

If in the spaces, how are they specially protected

Are any switches or fuses fitted in bunkers **No.**

Cargo light cables, whether portable or permanently fixed **Portable** How fixed **Connected to plug boxes**

In vessels fitted on the single wire system, how is the dynamo terminal fixed to the hull of vessel **2 Wire Throughout**

How are the returns from the lamps connected to the hull

Are all the joints with the hull in accessible positions

Is the installation supplied with a voltmeter **Yes** and with an amperemeter **Yes**, fixed **Main Switchboard**

VESSELS BUILT FOR CARRYING PETROLEUM.

In vessels built for carrying petroleum, are all switches and fuses fitted in positions not liable to the accumulation of petroleum vapour or gas **Yes**

Are any switches, fuses, or joints of cables fitted in the pump room or companion **No.**

How are the lamps specially protected in places liable to the accumulation of vapour or gas **No Lamps so placed.**

The copper used is guaranteed to have a conductivity of not less than that of the Engineering Standards Committee's standard, and the wires are protected by tinning from the sulphur compounds present in the insulating material.

Insulation of cables is guaranteed to have a resistance of not less than **600** megohms per statute mile at 60° Fahrenheit after 24 hours' immersion in water, the test being made after one minute's electrification at not less than 500 volts and while the cable is still immersed. **All in accordance with Navy Specification #15 C I D**

The foregoing statements are a correct description of the Electric Light installation fitted by us on this vessel and we declare that it is at this date in good order and safe working condition.

H. Loffat

Electrical Engineers

Date *Mar. 16/1921*

COMPASSES.

Distance between dynamo or electric motors and standard compass **200 Ft.**

Distance between dynamo or electric motors and steering compass **200 Ft.**

The nearest cables to the compasses are as follows:—

A cable carrying 2.8 Amperes	6 Ft.	feet from standard compass	12	feet from steering compass
A cable carrying .56 Amperes	1 Ft.	feet from standard compass	1	feet from steering compass
A cable carrying _____ Amperes	_____	feet from standard compass	_____	feet from steering compass

Have the compasses been adjusted with and without the electric installation at work at full power **Yes**

The maximum deviation due to electric currents, etc., was found to be **Nil** degrees on _____ course in the case of the standard compass and **Nil** degrees on _____ course in the case of the steering compass.

H. Loffat
SUPERINTENDING ENGINEER

Builder's Signature.

Date *Mar. 16/1921*

GENERAL REMARKS.

The installation has been fitted in accordance with the Standard Marine Rules of the American Institute of Electrical Engineers. Materials & workmanship are good. In my opinion the vessel is eligible for the notation "Elec Light."

Allen Lawrence
Surveyor to Lloyd's Register of Shipping.

Fee \$200. Chgd on machy acct.

Committee's Minute

New York APR 12 1921

FRI JUN 16 1922
FRI JUN 15 1923

© 2020

Lloyd's Register Foundation

THE SURVEYORS ARE REQUESTED NOT TO WRITE ACROSS THIS MARGIN.

2m.1110—Transfer.