

COPY.

Lloyd's Register of Shipping.

71, Fenchurch Street, E.C. 3.

19th July, 1929.

Dear Sirs,

M. With reference to the conversation which has passed today with Mr. Wilson, your Marine Superintendent, regarding the Tankers "CADELAC" & "SARANAC", it is understood that he desires to be informed if the shelf plate, at present fitted on the centre line bulkhead at the second deck level, on the caulking side of the bulkhead, may be removed.


In reply thereto I have pleasure in stating that provided horizontal gusset plates .44" in thickness be fitted, the shelf plate in question may be removed as desired, it being understood that the 8" bulb angle horizontal on the opposite side of the centreline bulkhead, as indicated on the approved plans, will remain.

I am, Dear Sirs,

Yours faithfully,

Messrs. The Anglo-American Oil Co. Ltd.,
36, Queen Anne's Gate,

S.W.1.



© 2020
Secretary.

Lloyd's Register
Foundation

W 80-0034