

THU. 18. JAN. 1917

pt. 13.

Received at London Office

REPORT ON ELECTRIC LIGHTING INSTALLATION. No. 9589

Port of Middlesbrough Date of First Survey and Date of Last Survey While building No. of Visits
 No. in on the Iron or Steel S.S. ASHLEAF Port belonging to London
 Reg. Book Built at Stockton By whom Messrs. Roper & Sons When built 1917
 Owners Lane & Macandrew Ltd Owners' Address London
 Card No. 505 Electric Light Installation fitted by Messrs. Clarke Chapman & Co. Gateshead When fitted 1917

DESCRIPTION OF DYNAMO, ENGINE, ETC.

One compound Enclosed Vertical Engine direct coupled to a continuous current compound wound Dynamo. (4 pole) - 400 R.P.M.

Capacity of Dynamo 250 Amperes at 100 Volts, whether continuous or alternating current continuous

Where is Dynamo fixed in Dynamo Room Whether single or double wire system is used Double

Position of Main Switch Board Near Dynamo having switches to groups A. B. C. D. & E of lights, &c., as below

Positions of auxiliary switch boards and numbers of switches on each Each light & group of lights provided with switches as required. (7 circuits = Midships; Forward; Wireless; Workshop; E & B Rooms; aft; Projector)

If fuses are fitted on main switch board to the cables of main circuit Yes and on each auxiliary switch board to the cables of auxiliary circuits Yes and at each position where a cable is branched or reduced in size Yes and to each lamp circuit Yes

If vessel is wired on the double wire system are fuses fitted to both flow and return wires or cables of all circuits including lamp circuits Yes

Are the fuses of non-oxidizable metal Yes and constructed to fuse at an excess of 50 per cent over the normal current

Are all fuses fitted in easily accessible positions Yes Are the fuses of standard dimensions Yes If wire fuses are used

Are permanent instructions fitted on or near each switch board giving particulars of proper size of fuse for each circuit Yes

Are all switches and fuses constructed of incombustible materials and fitted on incombustible bases Yes, slate & porcelain

Total number of lights provided for 195 arranged in the following groups :-

Group	Description	Number of Lights	Each of	Candle Power	Requiring a total current of	Amperes
A	lights	76	16	42.5	42.5	Amperes
B	lights	44	16	24.6	24.6	Amperes
C	lights	41	16	22.9	22.9	Amperes
D	lights	34	16	19	19	Amperes
E	Wireless	-	-	30	30	Amperes
2	Mast head light with 1 lamp	1	32	2.2	2.2	Amperes
2	Side light with 1 lamp	1	32	2.2	2.2	Amperes
6	Cargo lights of	6-16	-	incandescent	-	-

If arc lights, what protection is provided against fire, sparks, &c. 2-15amp Arc Lamps, enclosed type, with clear glass lanterns.

Where are the switches controlling the masthead and side lights placed in Wheel House.

DESCRIPTION OF CABLES.

Main cable carrying 250 Amperes, comprised of 34 wires, each 12 S.W.G. diameter, .300 square inches total sectional area

Branch cables carrying 42.5 Amperes, comprised of 19 wires, each 16 S.W.G. diameter, .060 square inches total sectional area

Branch cables carrying 24.6 Amperes, comprised of 7 wires, each 14 S.W.G. diameter, .035 square inches total sectional area

Leads to lamps carrying .56 Amperes, comprised of 1 wires, each 18 S.W.G. diameter, .0018 square inches total sectional area

Cargo light cables carrying 3.3 Amperes, comprised of 178 wires, each 38 S.W.G. diameter, .00502 square inches total sectional area

DESCRIPTION OF INSULATION, PROTECTION, ETC.


Vulcanized India Rubber taped & braided & lead covered where exposed steel armoured overall.

Joints in cables, how made, insulated, and protected No joints except mechanical ones.

Are all the joints of cables thoroughly soldered, and the flux used not containing acids or other corrosive substances Yes Are all joints in accessible positions, none being made in bunkers, cargo spaces, or spaces which may at any time be used for carrying cargo, stores, or baggage Yes. No.

Are there any joints in or branches from the cable leading from dynamo to main switch board No

How are the cables led through the ship, and how protected Lead covered cables run in Galvanized Iron pipes under fore & aft gangway & clipped to same with strong W. I. clips.



W470-0107

DESCRIPTION OF INSULATION, PROTECTION, ETC.—continued.

Are they in places always accessible *Yes*

What special protection has been provided for the cables in open alleyways or where exposed to weather or moisture *Lead covered cables run in Galvanized Iron Pipes.*

What special protection has been provided for the cables near galleys or oil lamps or other sources of heat *Lead covered & Armoured cables.*

What special protection has been provided for the cables near boiler casings " " " "

What special protection has been provided for the cables in engine room " " " "

How are cables carried through beams *in lead bushes* through bulkheads, &c. *in W. I. Bulkhead Glands.*

How are cables carried through decks *in Galvanized Iron Deck Tubes.*

Are any cables run through coal bunkers *Yes* or cargo spaces *Yes* or spaces which may be used for carrying cargo, stores, or baggage *Yes*

If so, how are they protected *Lead covered cables in Galvanized Iron Pipes*

Are any lamps fitted in coal bunkers or spaces which may at times be used for cargo, coals, or baggage *No*

If so, how are the lamp fittings and cable terminals specially protected —

Where are the main switches and fuses for these lights fitted —

If in the spaces, and are they specially protected —

Are any switches or fuses fitted in bunkers *No*

Cargo light cables, whether portable or permanently fixed *portable* How fixed *to W. I. Connection Boxes*

In vessels fitted on the single wire system, how is the dynamo terminal fixed to the hull of vessel *Double wire system*

How are the returns from the lamps connected to the hull —

Are all the joints with the hull in accessible positions —

Is the installation supplied with a voltmeter *Yes*, and with an amperemeter *Yes*, fixed *on Switchboard*

VESSELS BUILT FOR CARRYING PETROLEUM.

In vessels built for carrying petroleum, are all switches and fuses fitted in positions not liable to the accumulation of petroleum vapour or gas *Yes*

Are any switches, fuses, or joints of cables fitted in the pump room or companion *No.*

How are the lamps specially protected in places liable to the accumulation of vapour or gas *Special Gas Light Brass Fittings*

The copper used is guaranteed to have a conductivity of not less than that of the Engineering Standards Committee's standard and the wires are protected by tinning from the sulphur compounds present in the insulating material

Insulation of cables is guaranteed to have a resistance of not less than *600* megohms per statute mile at 60° Fahrenheit after 24 hours' immersion in water, the test being made after one minute's electrification at not less than 500 volts and while the cable is still immersed.

The foregoing statements are a correct description of the Electric Light installation fitted by us on this vessel and we declare that it is at this date in good order and safe working condition.

For Clarke, Chapman & Co., Ltd.

W. W. Woodcock

Electrical Engineers

Date *January 11th 1917*

COMPASSES

Distance between dynamo or electric motors and standard compass *192 ft*

Distance between dynamo or electric motors and steering compass *186 ft*

The nearest cables to the compasses are as follows:—

A cable carrying	<i>.56</i>	Amperes	<i>12</i>	feet from standard compass	<i>6</i>	feet from steering compass
A cable carrying	<i>.56</i>	Amperes	<i>6</i>	feet from standard compass	<i>12</i>	feet from steering compass
A cable carrying	—	Amperes	—	feet from standard compass	—	feet from steering compass

Have the compasses been adjusted with and without the electric installation at work at full power *Yes (South wired)*

The maximum deviation due to electric currents, etc., was found to be *Nil* degrees on *all* course in the case of the standard compass and *Nil* degrees on *all* course in the case of the steering compass.

ROPNER & SONS, LIMITED,

Builder's Signature. Date *Jan 15/17*

GENERAL REMARKS.

This installation has been fitted in accordance with the rules, is of good materials and workmanship and on completion was tested under full working conditions and found satisfactory

THE RECORD ELEC. LIGHT.

J. W. D.

W. Morrison

Surveyor to Lloyd's Register of British and Foreign Shipping.

Committee's Minute TUE JAN 23 1917 FRI 4 MAY 1917



received to start on the and The fitted of office durat trial worked no used by The