

COPY.

# Lloyd's Register of Shipping.

Port MONTREAL, P.Q.

October 1st. 1940.

This is to Certify that

I.J. TAIT,

the undersigned Surveyor to this Society did at the request of

the Owners' representative, on September 14th and subsequent dates survey the steel screw steamer "LOCK LOMOND", 5452 tons gross register of Glasgow, for the purpose of ascertaining the nature and extent of damage stated to have been sustained on August 28th 1940 on account of collision in convoy (name of vessel unknown).

A survey has already been held at Leith and cement boxes fitted over damaged parts above fore peak flat (port and starbd). It has been recommended that the temporary repairs then done be further examined and dealt with on return to United Kingdom. The Owner decided to deal with them here.

On examination of the vessel on September 14th while the vessel was lying afloat at Laurier Pier, Montreal, after the cement box on the starbd. side was removed, the undersigned Surveyor FOUND:

## DAMAGE

### PERMANENT REPAIRS

Starbd. side:

2nd strake below sheer plate No.1

torn.

3rd " " " " "

Nos. 1,2,3,4,& 5 frames above fore peak flat badly buckled.

### TEMPORARY REPAIRS

Bow plating (p & s) from light load line to 2nd strake below sheer and numerous rivets & seams leaking.

## RECOMMENDED

To be renewed.

" " "

To crop and part renew.

All started rivets & seams to caulk or weld as found necessary. All leaking tank top clips & rivets on fore peak flat to weld as necessary.

Owing to the fact that no drydock was available it was recommended that the damaged bow plating, now temporary repaired, be permanently repaired at Owners' convenience.

I.J. TAIT

Surveyor to Lloyd's Register.

Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:—  
The Committees of the Society use their best endeavours to ensure that the functions of the Society are properly to be understood that neither the Society nor any Member of any of its Committees is under any circumstances to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."