

COPY.

Lloyd's Register of Shipping.

71, Fenchurch Street, E.C.3.

Enclosure.

14th June, 1937.

Dear Sirs,

E.

I duly received your letters of the 3rd and 8th instant respecting the Boiler No.6256 proposed by Messrs. Stockton Chemical Engineers & Riley Boilers Ltd., for Messrs. Wm.Doxford & Sons' Yard No.640, and have to acquaint you that the plan (No.441) of this cylindrical boiler will be approved for a working pressure of 120 lb. per sq. inch, provided the boiler be constructed under the usual conditions of survey and testing.

The Steel Testing Surveyors should be advised regarding the tensile strength of the shell plates and butt straps, viz:- 29-33 tons per sq. inch.

It is noted that the thickness of the plain tubes are to be increased from 10 W.G. to 8 W.G.

One copy of the plan now approved is returned herewith, and the originally approved plan No.476 has been cancelled.

I am, Dear Sirs,

Yours faithfully,

The Surveyors,

MIDDLESBROUGH.



Lloyd's Register  
Foundation  
Secretary.

W983-0135