

COPY.

Lloyd's Register of Shipping.

71, Fenchurch Street, E.C.3.

Enclosure.

29th May, 1937.

Dear Sirs,

E.

Messrs.S.P. Austin & Son's Yard No.344.
The N.E. Marine Eng. Co's Contract No. 2885.

I return herewith one copy of the plan, forwarded with your letter of the of the 24th instant, of Boiler Pipe Arrangement proposed in connexion with the above contract, and I have to inform you that this plan will be approved for a working pressure of 220 lb. per square inch, provided all pipes and fittings where subjected to steam of a temperature above 425°F. be made of steel at an approved Works and tested as required by the Rules, the pipes be fitted as shown on the plan and be constructed under the usual conditions of survey and testing, and the drainage arrangements be to your satisfaction.

I have to add that, if the mixing/^{steam}valves (F7 and F8) be of the screw-down type, you should satisfy yourselves, on trial, that the temperature in the auxiliary steam line does not exceed 425°F., and a notice-board should be fitted near this valve, stating "After the new engines have been run in and are working under full superheat, this

COPY.

-2-

Messrs. S.P. Austin & Son's
Yard No. 344.

valve is only to be opened in an emergency".

I am, Dear Sirs,

Yours faithfully,

Secretary.

The Surveyors,
SUNDERLAND.



© 2020

Lloyd's Register
Foundation

W983-0290^{2/2}