

Lloyd's Register of Shipping.

Collingwood Buildings, Newcastle-on-Tyne. 1

LLOYD'S REGISTER
RECEIVED
- 1 MAR 1933

28th February 1933.

The Secretary, *And: ✓*

LONDON.

Dear Sir,

s.s. "JACOBUS".

We have to inform you that a Timber Assignment is required for the above vessel.

The particulars of fittings are as follows :-

Rule 86:

Poop and forecastle fitted.

Rule 88:

Nos. 3, 4, & 5 D.B. tanks have watertight centre girder. Wood plugs have been fitted in No. 2 tank. ✓

Rule 89:

The bulwarks are 5'-0" in height with 7" x 3" B.A. stays spaced 5'-9" apart. The rail is 7" x 3" B.A. ✓

Rule 90:

The steam and hand steering gear is in the poop space. ✓

Rule 91:

Eyeplates for lashings are riveted to the sheerstrake spaced 9'-9" apart. The end eyeplates are spaced not more than 6'-6" from superstructure ends. Angle sockets spaced 9'-9" are fitted to the stringer plate.

We are, Dear Sir,

Yours faithfully, ✓

THE SURVEYORS,

per

P. D. Brindley

*Special Survey done
Completed*

© 2020
Lloyd's Register
Foundation

W984-0139

Referred to the Chief Ship Surveyor.
(Freeboard).

Handwritten signature

1 MAR 1933

Handwritten text: 2000000000

Handwritten text: 1000000000

Handwritten text: 1000000000

© 2020

Lloyd's Register
Foundation

