

REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL) 10 AUG 1928

Received at London Office

Date of writing Report 19... When handed in at Local Office - 9 AUG 1928 Port of SUNDERLAND.

No. in Survey held at SUNDERLAND. Date, First Survey 5th June Last Survey 1st July 1928. (Number of Visits 5)

Reg. Book. Suppl. 89008 on the S.S. AMBERTON Tons Gross 5844 Net 3245

Built at Sunderland. By whom built Short Bros Ltd. Yard No. 431 When built 1928.

Owners R. Shephman & Sons. Port belonging to Newcastle.

Electric Light Installation fitted by Blake Shephman & Co Ltd. Contract No. 431. When fitted 1928.

System of Distribution Double wire.

Pressure of supply for Lighting 110 volts, Heating - volts, Power - volts.

Direct or Alternating Current, Lighting Direct. Power -

If alternating current system, state frequency of periods per second -

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off yes.

Generators, do they comply with the requirements regarding overload yes, are they compound wound yes.

are they over compounded 5 per cent. yes, if not compounded wound state distance between each generator -

Where more than one generator is fitted are they arranged to run in parallel no, is an adjustable regulating resistance fitted in series with each shunt field yes.

Are all terminals accessible and clearly marked yes, are they so spaced or shielded that they cannot be accidentally earthed, or short circuited yes.

Position of Generators Engine Room starboard side. Are the lubricating arrangements of the generators as per Rule yes.

is the ventilation in way of the generators satisfactory yes, are they clear of all inflammable material yes.

if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators - and - are the generators protected from mechanical injury and damage from water, steam or oil yes.

are their axis of rotation fore and aft yes

Earthing, are the bedplates and frames of the generating plant efficiently earthed yes, are the prime movers and their respective generators in metallic contact yes.

Main Switch Boards, where placed Engine Room starboard side near dynamo.

If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard yes.

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes yes

are they protected from mechanical injury and damage from water, steam or oil yes, if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards - and -

are they constructed wholly of durable, incombustible non-absorbent materials yes, is all insulation of high dielectric strength and of permanently high insulation resistance yes.

if semi-insulating material is used, are all conducting parts connected to one pole insulated from the slab with mica or micanite and the slab similarly insulated from its framework yes, and is the frame effectively earthed yes.

Are the following fittings as per Rule, viz. :- spacing or shielding of live parts yes, accessibility of all parts yes, absence of fuses on back of board yes, proportion of omnibus bars yes.

individual fuses to voltmeter, pilot or earth lamp yes, connections of switches yes.

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches Double pole switches & fuses in dynamo mains. Single pole switches & double pole fuses in each outgoing circuit.

Instruments on main switchboard One ammeters. One voltmeters. - synchronising device for paralleling purposes.

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system. Earth lamps coupled to earth through switches & fuses.

Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules. yes.

Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule. yes.

Insulation of Cables, state type of cables, single or twin *single* are the cables insulated and protected as per Tables III and IV of the Rules *yes*

Fall of Pressure, state maximum between bus bars and any point of the installation under maximum load *3.4 volts*

Cable Sockets and other connections, are the ends of all cables having a sectional area of 0.007 square inch and above provided with soldering sockets *yes*

Paper Insulated Cables, If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound *yes*

Cable Runs, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage *yes*

Support and Protection of Cables, state how the cables are supported and protected *head & armoured in Engine Room, head covered in salubrite, armoured & braided in cargo spaces clipped to underside of deck*

If cables are run in wood casings, are the casings and caps secured by screws *yes*, are the cap screws of brass *yes*, are the cables run in separate grooves *yes*. If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VI *yes*

Refrigerated Chambers, if lights are fitted, are the cables and fittings in accordance with the special requirements *yes*

Joints in Cables, state if any, and how made, insulated, and protected *none made*

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands *yes*

Bushes in Beams and Non-watertight Positions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed *yes*, state the material of which the bushes are made *head*

Earthing Connections, state what earthing connections are fitted and their respective sectional areas *yes*

are their connections made as per Rule *yes*

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule *yes*

Emergency Supply, state position and method of control of the emergency supply and how the generator is driven *yes*

Navigation Lamps, are these separately wired *yes*, controlled by separate switch and separate fuses *yes*

are the fuses double pole *yes*, are the switches and fuses grouped in a position accessible only to the officers on watch *yes*

has each navigation lamp an automatic indicator as per Rule *yes*, are separate screens provided for the use of oil and electric side lights *yes*

are separate oil lanterns provided for the mast head lights and side lights *yes*

Fittings, are all fittings on weather decks, in stowholds and engine rooms and wherever exposed to drip or condensed moisture, watertight *yes*

are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected *no*

are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected *no*

how are the cables led *yes*

where are the controlling switches situated *yes*

Searchlight Lamps, No. of *yes*, whether fixed or portable *yes*, are their fittings as per Rule *yes*

Arc Lamps, other than searchlight lamps, No. of *yes*, are their live parts insulated from the frame or case *yes*, are their fittings as per Rule *yes*

Motors, are their working parts readily accessible *yes*, are the coils self-contained and readily removable for replacement *yes*

are the brushes, brush holders, terminals and lubricating arrangements as per Rule *yes*, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material *yes*

are they protected from mechanical injury and damage from water, steam or oil *yes*, are their axis of rotation fore and aft *yes*

if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type *yes*, if not of this type, state distance of the combustible material horizontally or vertically above the motors *yes* and *yes*

Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed as per Rule *yes*

Lightning Conductors, where lightning conductors are required, are these fitted as per Rule *yes*

Ships carrying Oil having a Flash Point less than 150° F. Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings *yes*

If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office *yes*

PARTICULARS OF GENERATING PLANT.

DESCRIPTION OF GENERATOR.	No of	RATED AT				Revs. per Min.	DRIVEN BY.	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.	
		Kilowatts.	Volts.	Ampères.	Fuel Used.			Flash Point of Fuel.	
MAIN ...	1	8	110	72	350	Single cylinder Steam Engine			
AUXILIARY ...									
EMERGENCY ...									
ROTARY TRANSFORMER									

LIGHTING AND HEATING CONDUCTORS.

Ref. No.	DESCRIPTION.	No. of Conductors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current. Ampères.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
1	MAIN GENERATOR...	2	.06000	19	.064	72	20	Blue rubberhead covered	
	AUXILIARY GENERATOR								
	EMERGENCY GENERATOR								
	ROTARY TRANSFORMER...								
	AUXILIARY SWITCHBOARDS								
2	ENGINE ROOM ...	2	.00401	4	.036	6.5	50	" "	heads armoured
	BOILER ROOM ...								
3	Saloon & Steward	2	.01462	4	.052	13.6	208	" "	Armoured, braided
4	Engineers aft.	2	.00401	4	.036	12.5	80	" "	" "
5	WIRELESS ...	2	.01462	4	.052	25	210	" "	" "
	SEARCHLIGHT ...								
6	MASTHEAD LIGHT ...	2	.00152	1	.044	9	220	" "	" "
7	SIDE LIGHTS ...	2	.00152	1	.044	9	40	" "	lead covered.
8	COMPASS LIGHTS ...	2	.00152	1	.044	5	12	" "	" "
9	DECK LIGHTS ...	2	.00152	1	.044	9	250	" "	armoured, braided
10	CARGO LIGHTS ...	2	.00455	168	.38	2.5	100	" "	braided & banded
	ARC LAMPS ...								
	HEATERS ...								

MOTOR CONDUCTORS.

Ref. No.	DESCRIPTION.	No. of Motors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current. Ampères.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	BALLAST PUMP ...								
	MAIN BILGE LINE PUMPS ...								
	GENERAL SERVICE PUMP ...								
	EMERGENCY BILGE PUMP ...								
	SANITARY PUMP ...								
	CIRC. SEA WATER PUMPS ...								
	CIRC. FRESH WATER PUMPS ...								
	AIR COMPRESSOR ...								
	FRESH WATER PUMP ...								
	ENGINE TURNING GEAR ...								
	ENGINE REVERSING GEAR ...								
	LUBRICATING OIL PUMPS ...								
	OIL FUEL TRANSFER PUMP ...								
	WINDLASS ...								
	WINCHES, FORWARD ...								
	WINCHES, AFT ...								
	STEERING GEAR ...								
	WORKSHOP MOTOR ...								
	VENTILATING FANS ...								

All Conductors are of annealed copper conforming to British Standard Specification No. 7.
 The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.
 The foregoing is a correct description

For **CLARKE, CHAPMAN & Co. LTD.**

W. Taylor

Electrical Engineers.

Date *July 31, 1928.*

Director

COMPASSES.

Distance between electric generators or motors and standard compass *96 feet.*
 Distance between electric generators or motors and steering compass *90 "*

The nearest cables to the compasses are as follows:—

A cable carrying *5* Ampères *12* feet from standard compass *6* feet from steering compass.

A cable carrying *5* Ampères *6* feet from standard compass *12* feet from steering compass.

A cable carrying *-* Ampères *-* feet from standard compass *-* feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power *yes.*

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted *yes.*

The maximum deviation due to electric currents was found to be *nil* degrees on *all* course in the case of the standard compass, and *nil* degrees on *all* course in the case of the steering compass.

FOR **SHORT BROTHERS, LIMITED.**

Sheshon

Builder's Signature.

Date *Aug 3rd 1928*

Is this installation a duplicate of a previous case *yes* If so, state name of vessels *S/S Bughton & S/S Rverton*

General Remarks (State quality of workmanship, opinions as to class, &c.)

The above installation is in accordance with the Society's Rules. The vessel is eligible in my opinion for notation elec light wireless.

It is submitted that this vessel is eligible for THE RECORD.

elec light.

W.T. Budgett. 11/8/28.

Total Capacity of Generators *8* Kilowatts

The amount of Fee ... £ *8* : : *9 July 19 28*
 Travelling Expenses (if any) £ : : *11. 8. 28*

W.T. Budgett.

Surveyor to Lloyd's Register of Shipping.

Committee's Minute

Assigned

Elec light

5c, 12, 53.—Transfer.
 (The Surveyors are requested not to write on or below the space for Committee's Minute.)



© 2020

Lloyd's Register Foundation