

Steel Screw Steamers Nos. 991 and 992 proposed to be built by
Messrs. Palmers Shipbuilding & Iron Co. Ltd., with a view to
class 100A1 "with freeboard".

Rule Dimensions : 415 x 55.5 x 37 to upper deck
28.25 to second deck

Rule depth = 36.25

Scantling Numbers : 15043 and 38076

Proportions : Length = 11.21 depths to upper deck.

Plans of midship section, profile and decks and
arrangements at the forward and after peaks have been submitted
by the Builders direct.

These vessels are of the complete superstructure
type, with tonnage opening. There are two steel decks. The
double bottom is 6" deeper than required by the Rules.

There are no deep tanks in these vessels, and
there is no indication of any concentration of loading amidships.

The scantlings and arrangements have been discussed
in this Office with Mr. Dodds, representing the Builders, and
it is submitted that provided

COMPLIANCE

the vessels will be eligible to be classed 100A1 with a draught
corresponding to a freeboard not exceeding that contemplated
by the Rules for a complete superstructure vessel having a
tonnage opening.

K. G. R. W.

19.12.28

W. R. W.



© 2020

Lloyd's Register
Foundation

W9938-0167