

COPY.
PORT OF SHEFFIELD

DAVY BROTHERS LIMITED

PARK IRON WORKS

SHEFFIELD

FL/RD

2nd November, 1932

Lloyd's Register of Shipping,
Orchard Chambers,
Church Street,
SHEFFIELD

Dear Sirs,

M.S. Air Receiver 16" dia. to the order of
Messrs. A. & E. Woodward, Hull.

Referring to our conversation with your Mr. Black this morning, we have pleasure in enclosing herewith print of our amended drawing No. B.10305 showing details of the above air receiver.

Please note that owing to the difficulty of rivetting in the last end as originally shown on our sketch No. 67/AH. already in your possession, we propose to reverse the bottom end i.e. dished inwards instead of outwards.

The actual tensile strength of this plate is 28.4 tons with an elongation of 29% in 8 inches, which gives us a working pressure of 272 lbs. per square inch against 260 lbs. as which the receiver will work.

We shall be glad if you will submit the drawing to your London Office, at the same time asking them to wire you tomorrow morning their approval or otherwise, so that there will be no delay in the manufacture as our clients are pressing us very strongly for delivery.

We have written Messrs. Woodward Ltd., today informing them of our proposals, and enclosing copy of our drawing.

Yours faithfully,
For Davy Brothers Limited.

Purchasing Agent.



© 2018

Lloyd's Register
Foundation