

Newcastle

5th August 1893

A. Menalloy

The Owners of the Screw
Steamer "Maurice" of London
1893 (was examined the said vessel
on the 21st of June 1893 while lying
in Smith's Bay near Co. Down
about North Shields. in order to
ascertain the extent of damage
stated to have been done by grounding
on the 14th of June 1893. Particulars
of which (See Log Book), and
on examination found as follows.
Several plates extending along the
Range of the Keel and bottom
very much indented. And a large
number of rivets on shell plating
stowed, and breaking. The plates
chased off Keel and bottom and
a four inch keel together with
a three inch keel however fine.
Recommended that the damaged
plating be removed and replaced



© 2018

Lloyd's Register
Foundation 191

ascertain the condition of the Floors
and framework.

On the 30th of June again
visited the vessel, and found three
floors buckled and twisted, several
frames on each side together with
intercostal plates bent.

Recommended that one Aul plate
be renewed, one cut off fairied and
replaced, and one fairied in place.
On Starboard bottom, three plates be
cut off fairied and replaced, and
five fairied in place (Port bottom)
that one plate be renewed, five cut
off fairied and replaced, and nine
fairied in place. That one Floor
plate be renewed, one cut out fairied
and replaced and one fairied in place
That thirteen frames on the Port-
side, and four on the Starboard
be fairied in place together with
several intercostal plates on each
side, that all staked and leary
ribs be renewed, landing edge
and butt caulked. Ballast tanks
Copper lined, and oil Compartments
lined by water pressure. That
a New lower anchor, and steel
wire hawser be supplied, and



© 2018

Lloyd's Register
Foundation

The bottom of the new coat
with paint in order to place her
in as good condition as before
the accident.

Fee £3.30

To Manxton



© 2018

Lloyd's Register
Foundation 193