

No. 3404

Report of Survey for Repairs, &c., of Engines and Boilers.

MON. 26 AUG 1895

Date of writing Report August 22nd 1895 When handed in at Local Office Hamburg Port of Hamburg

No. in Reg. Book 31 Survey held at Hamburg Date, First Survey August 19th 1895 Last Survey August 21st 1895

31 on the Machinery of the Wood, Iron or Steel S. 3 Met. St. Bakuin Master W. Ashfield

Tonnage { Gross 1669 Net 1093 Vessel built at W. Harlepool By whom W. Gray & Co. When 1886. 6.

Registered Horse Power 213 Engines made at W. Hpl When 1886 Boilers, when made (Main) 1886 (Donkey) 1886

No. of Main Boilers 2 Owners Abraham Frank & Sons & (Lini) Port London Voyage S. Shields

No. of Donkey Boilers 1 If Surveyed Afloat or in Dry Dock afloat

Steam Pressure in Main Boilers 150 lbs. in Donkey Boilers 90 lbs.

Particulars of Classification (which must be inserted precisely as in Register Book & Supplements).

Last Survey No. _____ Port _____ Part of annual _____

Particulars of Examination and Repairs (if any) survey of Boilers

(Periodical Surveys, when held, must be reported in detail and serially in the terms of the Rules. State clearly the cause of Repairs, if any, and, in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage (the cause of which must be stated) should be separated from Repairs due to other causes; and besides being detailed in the body of the report, should be briefly summarized at the end of the report. State also the dates and initials of any letters respecting this case.)

Did the Surveyor personally go inside each Main Boiler separately and make a thorough examination at this time? Yes

Do. " " Donkey " No.

If this was not done, state for what reasons? The Donkey Boiler was too hot for internal inspection

And what parts of the Boilers could not be thus thoroughly examined? Donkey Boiler inside

Also what special means, in the absence of internal examination, were adopted by the Surveyor to assure himself of the thorough efficiency of those parts of each Boiler? None

Did the Surveyor examine the Safety Valves of the Main Boiler? Yes.

At what pressure were they afterwards adjusted under steam? 150 lbs.

Did the Surveyor examine the Safety Valves of Donkey Boiler? No.

To what pressure were they afterwards adjusted? 90 lbs.

If the Survey is not complete state what arrangements have been made for its completion? Will be completed on the Tyne.

I examined the main Boilers inside and outside and found them satisfactory with exception of 19 screw stays in the Boiler and 38 screw stays in Port Boiler at sides and backs of combustion chambers, which are to be replaced by new ones. The deformation of the furnaces is apparently unchanged since last Survey, under steam I found the Boilers tight and adjusted the safety valves as above.

I examined the Donkey Boiler under steam, found it tight and the safety valves correctly adjusted.

The H. P. cylinder cover was found cracked round the flange and was temporarily secured for the voyage to the Tyne.

The Newcastle Surveyors have been advised that the Boiler Survey is to be completed, and a new cylinder cover is to be fitted at their Port. For completion of B.S. remains, fitting of 57 screw stays to main Boilers, examination of Donkey Boiler inside and overhauling of safety valves of same.

General Observations, Opinion, and Recommendation:—
 (State clearly what alteration, if any, is suggested to be made in the existing classification of the vessel's machinery in the Register Book, consequent upon this survey, and also any alteration required to be made in the records of the vessel's machinery, boilers, working pressures, &c.; thus, for example, B.S. 101, B.&N.S. 101 or 102, 104, 110 lb., F.D., &c.)

With regard to the parts passed I beg to recommend that B.S. be entered in the Register Book, but that the case be deferred until a satisfactory Report has been received from the Newcastle Surveyors.

Office or Registration Fee (per Sec. 27) £ 10. 0

Survey Fee (per Section 28) £ 2. 2. 0

Special Damage Fee (per Section 28) £ : :

Travelling Expenses (if chargeable) £ : :

Fees applied for 22/2 1895

Received by me, M. B. B.

State if Certificate is required No

Committee's Minute TUES. 27 AUG 1895

Assigned Deferred

Engineer Surveyor to Lloyd's Register of British and Foreign Shipping. M. B. B.

Sh. Riick

FRI. 1 NOV 1895

State if a Report is also now sent on the Ship or if not whether, and when, one will be sent.

See Agents to be

14-LRVT-... The Surveyors are requested not to write on or below the space for Committee's Minute.

Insert Character of Ship and Machinery precisely as in the Register Book.