





Port of NewcastleContinuation of Report No 43821 dated2 JUL 1902

on the

S.S. "Baku Standard"

Cables raised with Winch, masts (doublet masts) spars, etc. etc. per full connections. General equipment made good & satisfactory.

Repairs now done due to wear & tear:-

Tank top plates on Port side under Boilers entirely renewed also a number of tank top plates on Starboard side: floor plates & centre plates in way of above cut & partly renewed, also intercostals in way of same. After repairs were effected tank tested as required by Rules & made satisfactory.

1 Shell plate, forward, on Starboard side in way of 1st Peak renewed also a number of deck plates shell rivets renewed; 3 Lower Bulkhead plates renewed & 1 Corrugated plate fitted in way of 1st deck bulkhead.

M. S. Seddon.