

SWAN, HUNTER, & WIGHAM RICHARDSON, LTD

SHIP, ENGINE & FLOATING DOCK

BUILDERS AND REPAIRERS.

WALLSEND & WALKER-ON-TYNE.

LONDON OFFICE: 150, LEADENHALL ST. E.C.

I.H.

PLEASE ADDRESS YOUR REPLY TO

WALLSEND-ON-TYNE.

3rd May, 1904.

Tuesday.

H. J. CORNISH, Esq.,

Messrs. LLOYDS REGISTRY,

LONDON, E.C.

Dear Sir,

760' x 87'-6" x 60'-0" mld.

Would you be good enough to inform me by return whether you will be disposed to pass inch steel rivets in 20/20ths shell plates where the rivets will be laid up by hand, viz: between the tank margin and upper deck sheerstrake; the overlaps being treble rivetted. I am aware that the rule provides for 1 1/8" rivets for this thickness of plate, but on referring the matter to Mr. Stephenson he considers that inch rivets will make the better job where laid up by hand. The diameter of the rivets where hydraulic will be used we propose to make 1 1/8" as per rule

We are, dear Sir,

Yours faithfully,

For

SWAN, HUNTER, & WIGHAM RICHARDSON, LIMITED.

*T. W. Deane*

Telegraphic & Cable Address: "HUNTER, WALLSEND." CABLE CODES: WESTERN UNION, WATKINS & APPENDIX, SCOTT'S, A.B.C. & A.I.

Nos 2 AND 80 WALLSEND for local Messages.

No 2027 NEWCASTLE ON TYNE for Trunk Messages only.

Telephones: POST OFFICE No 411. NATIONAL

Passenger Railway Stations: WALLSEND AND CARVILLE.



© 2018

Lloyd's Register Foundation