

Messrs. Swan, Hunter & Wigham Richardson's S.S. No. 735.

It is submitted the Builders be informed that the approved plan of cast steel stem piece has been received.

With reference to the proposal to dispense with the double angle attachment to the margin plate in view of double angles being fitted to the tank top and face of tank side knees, it should be pointed out that these latter double angles take the place of the continuous plate which was previously proposed to be fitted in addition to the double angles at the margin plate.

As it is of the utmost importance that the connections at the bilge where the frames are cut shall be such as will give the highest degree of efficiency, it is considered that double angles should be fitted to the margin plate as previously required.

It is noted that deck plans are in progress.

Mr. 18.7.04
Amended 19th
Sp.c. to M.W.C.

J.W.H.
19/7/04
C.F.

B