

to Chief Surveyor

14/11/92.

Received from Chief Surveyor

MESSEL'S NAME

Thermopylae

Report HKg No. 1074

The remarks of the Chief Surveyor are desired on this Case for the consideration of the Classing Committee.

"The endorsement to contain a detailed summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement." - Extract from Sub-Committee's Report, 24/5/92.)

of Survey

S.S. (Composite) ft

The requirement of the Rules for Special Survey of composite vessels have been complied with. all close caulk removed.

Cement reviewed in fore & after ends of vessel, and in 100 other frame spaces where removed for survey. 74 wasted rivets removed from now doubled. A number of rivets reviewed. 60 broken metal bolts reviewed. worn ends of pumps cut off & leader ends fitted. Rivets reviewed. all metal sheathing entirely stripped.

Bottom re-caulked and re-sheathed with 4 m on felt.

The main deck has been bored and found to be less than 3" thickness and therefore requires to be reviewed. It is however reported to be in good condition.

It is submitted the Owner should be informed that on account of the deck being worn down below the limit of thickness admitted by the Rules it is necessary for the same to be renewed to render the vessel eligible to retain her class and they should be requested to state when and where they propose to have this done.

When the deck has been renewed the vessel will be eligible to have record of survey 10.92 and notation S.S.HKg 92 also record of 27Y/M 10.92



© 2018

Lloyd's Register
Foundation

14.11.92.

WILLIAM



LR-FAP-SAS6-54

© 2018
Lloyd's Register
Foundation