

REPORT of SURVEY for REPAIRS, &c.

33,151

No. in Reg. Book. **No. 35151** Survey held at **London** Date, first Survey **28th Oct** Last Survey **19th Nov** 1875
 1317 on the **"Cutty Sark"** Master **W. Tiptaft**
 TONNAGE under Tonnage Deck **892** Built at **Dumbarton** When built **1869**
 Ditto of Spar Deck, or Loading Deck **55.81** Owners **Willis** Port belonging to **London**
 Ditto of Poop **15.16** Residence
 Ditto of Raised Quarter Deck **962.97** By whom built **Scott** Destined Voyage
 Gross Tonnage **41.56** If Surveyed Afloat or in Dry Dock **dry dock & afloat**
 Register Tonnage, cut on Beam **921.79**
 Engine Room
 Reg. Tonnage as Sp' mer, cut on Bm.
 Length of Poop **46.6** ft. Ditto, Forecastle **—** ft. Ditto, Raised Quarter Deck **—** ft.
 Last Survey, No. **193501** Port **London** Years assigned **16** Character in Register Book **A1**
 REPAIRS, OR EXAMINATION AS PER RULE **first Special Survey for Composite Vessels.**

Yellow Metal stripped off. The timber beams and Ceiling equal to one plank removed on each side. The Cement & examined and found in good condition. Two additional painting Beams introduced owing to slight movement forward below Hold Beams. Caulked from keel to upper part of Wales and Rebutted over felt as before.

This Ship has two Bulbheads.

Present Condition of the	Good	Requires Bolt	Good	Windlass and Capstan	Good
Decks					
Waterways	dc	Breasthooks and Stemson	dc	Pumps	dc
Comings	dc	Transoms, Pointers, and Crutches	dc	Boats	dc
Upper Deck Beams & Fastenings	dc	Timbers of the Frame at the openings	dc	Masts, Yards, &c.	dc
Lower Deck Beams & Fastenings	dc	Ditto Ditto at other places	dc	Condition, how ascertained	from deck
Planksheers	dc	Keelsons	dc	Sails	well found
Sheerstrakes	dc	Clamps and Shells	dc	Anchors	No. of 39. 15 & 20 fms
Topsides	dc	Ceiling	dc	Cables	Complete
Wales	dc	Rudder	dc	Hawsers and Warps	dc
Plank (Bottom) and Counter	dc	Copper	When put on	Standing & Running Rigging	good
Engine Room Skylights		Caulking of		Cargo and Main Hatchways	good
Coal Bunker, Openings, Lids, &c.		Bottom, Deck, & Waterways	Good	Hatches	Good
General Observations, Opinion as to Class, &c.					

This Ship being in good condition and the requirements of first special survey having been complied with we are of opinion she may remain as classed and the present survey recorded.

The Amount of Entry Fee ... £ 5 : 5 : received by me, **W. Edwards**
 27/11/75 Special ... £ 5 : 5 : 20.11.1875
 Certificate (if required) ... £ : :
 (Travelling Expenses, if any, £)
 Committee's Minute **3rd December 1875**
 Character assigned **A1**
S.S. 75 W. 75