

# Report of Survey for Repairs of Engines and Boilers.

No. 26860

No. in  
eg. Book. Survey held at

Liverpool

Date, first Survey 15<sup>th</sup> April Last Survey 3<sup>rd</sup> May 1879

153

on the

S.S. "Strathleven"

Master

C. Pearson

ons

1588

Owners Burnett & Son

Port belonging to

Glasgow

Classed

Years assigned. Character in Register Book.

100 A 1 9/77

Lloyd's M.C. 2-76

YEAR.

Diameter of Cylinders 10 3/8" 10 7/10"

Length of Stroke 42"

Engines made at

Glasgow

When made

Pressure of Steam 70

Registered Horse Power 220

By whom made

Blackwood & Gordon

Particulars of Repairs and Examination of Engines and Boilers in accordance with the requirements of the rules for special Survey No. 1 for Iron Ships. The cylinder covers and valve casing doors removed, pistons cylinders and valves examined and found good, pumps and condenser opened out examined and found in good order, Crank and intermediate shafting examined and found good, A new propeller shaft and stern tube bushes have been fitted, Sea cocks and chests overhauled, A reducing valve has been fitted between main and winch boiler on steam supply pipe.

Boilers opened out scaled cleaned, examined throughout and found in good order, Safety valves examined and put in good order, Donkey Boiler examined and found good.

The Machinery and Boilers of this vessel are now in a good and efficient condition and in my opinion entitle the vessel to retain the notification Lloyd's M.C. and to be marked from this date.

The Amount of Fee ... £ 4 : 4 : ... received by me, Certificate (if required) ... £ : 5 : 187

(Travelling Expenses, if any, £)

Committee's Minute Liverpool 7th 13-1880

100 A 1. Record 55 n<sup>o</sup> 1/79. Lloyd's M.C. in Port May/79

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.



Stratton

26860<sup>ss</sup>

This submitted that this  
hand is eligible to have  
the notation Lloyd

Inc 5-79 recorded

Miller

16/2/89



© 2018

Lloyd's Register  
Foundation