

REC'D. PERS. DEPT. 29 JAN 1963

28 JAN 1963

Rpt. C. 11 (Contd.)

Index No.

LLOYD'S REGISTER OF SHIPPING

Ship's Name " ORIENTAL QUEEN "

Official No.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in 1936

GANGWAY AND CARGO DOORS

1. Cargo door (stard.) between Frs. 43-45 F. removed at this time and the opening permanently plated over. New side shell frame fitted in way of original opening.

2. Gangway door fitted (p & s) between second and freeboard decks as follows:-

Frs. 38-40 A (p & s) - to 2nd Class Dining room.

Frs. 60-62 (F) (p & s) - to Accom. spaces, etc.

Each opening 1200 x 1900, suitably compensated and closed watertight by hinged steel doors.

SCUPPERS & DISCHARGES

Combined scupper and sanitary discharges (1 @ 160 Dia. & 1 @ 100 Dia. (p & s) also 1 @ 160 Dia. & 1 @ 130 Dia. (p)) from newly fitted W.C. and shower spaces on 2nd deck ford (p & s) and abreast Machy Casing (p) respectively led overboard below 2nd deck with bronze screw-down non-return valves at ship's side controlled from above freeboard deck with open/shut indicators.

COMPANIONWAYS

Companionway on upper deck leads to No. 2 tween deck accom. spaces, contained in strong steel casing fitted on top of No. 2 steel cargo hatch cover, hinged steel door, operated both sides, 1390 x 540, sill 200 (above top of steel hatch cover).

Companionway on superstructure deck leads to No. 5 tween deck accom. spaces contained in strong steel casing fitted on top of No. 5 steel cargo hatch cover, hinged steel door, operated both sides, 1390 x 540, sill 200 (above top of steel hatch cover).

LLOYD'S REGISTER
J.R. WILSON
SURVEYOR TO LLOYD'S REGISTER
YOKOHAMA
6th December 1962

Noted
29/1/63

Copy placed on board vessel.