

Boiler
endorsement

Shipbuilders: Messrs. Blythswood S.B. Co., Ltd. Yard No. 52

Makers: Messrs. John G. Kincaid & Co., Ltd

Boilers No. for
DIESEL ENG. N° K118/R

It is submitted that the plan of dry back cylindrical
boilers merits approval for a working pressure of 180 lb
per sq. inch, provided the boilers be constructed under the
usual conditions of survey and testing.

The Steel Testing Surveyors should be advised regarding
the tensile strength of the shell plates + butt straps
viz:- 29/33 tons per sq. inch

✓ four additional stay tubes be fitted at
the wide water space as indicated on the plan and /

Return plan (i)

Retain copy (i)

Im. 8.36 T.

✓ It should be pointed out that the fitting
of nuts at the combustion chamber end of
stay tubes is not in accordance with the Rules. S.A.
15/6/37