

COPY.

Lloyd's Register of Shipping.

71, Fenchurch Street, E.C.3.

Enclosure.

17th June 1937.

Dear Sirs,

Messrs. Kincaid's No.118 - Blythwood's No.52.

E. I return herewith one copy of the plan, forwarded with your letter of the 12th instant, of dry back cylindrical boilers proposed for the above contract, and with regard thereto I have to inform you that this plan will be approved for a working pressure of 130 lb. per sq. inch, provided four additional stay tubes be fitted at the wide water space, as indicated on the plan, and the boilers be constructed under the usual conditions of survey and testing.

I should point out that the fitting of nuts at the combustion chamber end of stay tubes is not in accordance with the Rules.

The Steel Testing Surveyors should be advised regarding the tensile strength of the shell plates and butt straps, viz:- 29/33 tons per sq. inch.

I am, Dear Sirs,

Yours faithfully,

The Surveyors,

GREENOCK.

Secretary.