

PARTICULARS OF LONGITUDINAL FRAMING.

| FRAMING. | | AMIDSHIPS. | | | ENDS. | | | Any Departure from Approved Plans to be Noted. | RIVETING. | | | | |
|---|--|--|-------|-------------------------------------|------------------|-------|---------------------|--|--------------------------------|----------------------|--|----------------------------------|----------------------|
| | | In Ship. | | LBS XXX | In Ship. | | LBS XXX | | Rivets in Longitudinal Frames. | | Spacing of Rivets on each side of Transverses and Bulkheads Inches. | Rivets in Brackets to Bulkheads. | |
| | | Ins. | Ins. | | Ins. | Ins. | | | Diam. Ins. | Spacing Ins. | | Number. | Diameter. Inches. |
| Framing of t, L-E | | | | | | | | | | | | | |
| Frames in Bridge 'tween Decks | | | | | | | | | | | | | |
| Frames from Uppermost Continuous Deck No. 1 | | 5 | 2 1/2 | 9.8 | 5 | 2 1/2 | 9.8 | 5X3X9.43Lbs. ✓ | 3/4 | 4/8 | 4 1/8 | 7 | 3/4 |
| " 2 | | " | " | " | " | " | " | " " " | " | " | " | " | " |
| " 3 | | " | " | " | " | " | " | " " " | " | " | " | " | " |
| MAIN DECK " 4 | | 5 | 2 1/2 | 9.8 | 5 | 2 1/2 | 9.8 | 5X3X9.43LBS. ✓ | " | " | " | " | " |
| " 5 | | " | " | " | " | " | " | " " " | " | " | " | " | " |
| LOWER DECK " 6 | | 7 | 3 1/2 | 13.6 | 7 | 3 1/2 | 13.6 | 7X3X13.6LBS. ✓ | " | " | " | " | " |
| " 7 | | " | " | " | " | " | " | " " " | " | " | " | " | " |
| " 8 | | " | " | " | " | " | " | " " " | " | " | " | " | " |
| " 9 | | " | " | " | " | " | " | " " " | " | " | " | " | " |
| BILGE No. 10-No. 13 | | 7 | 3 1/2 | 13.6 | 7 | 3 1/2 | 13.6 | 7X3X13.6LBS. ✓ | " | " | " | " | " |
| LONG. BHD. NO. 14-NO. 16 | | " | " | " | " | " | " | " " " | " | " | " | " | " |
| SIDE GIRDER NO. 17-NO. 19 | | " | " | " | " | " | " | " " " | " | " | " | " | " |
| " 13 | | | | | | | | | | | | | |
| " 14 | | | | | | | | | | | | | |
| " 15 | | | | | | | | | | | | | |
| " 16 | | | | | | | | | | | | | |
| Spacing of Longitudinal Frames | | Amidships | | 1'-8" to 2'-6" | At Ends | | 1'-8" to 2'-9" | | | | | | |
| Double Bottoms L, L or C | | Tank Top Longitudinals | | | Bottom | | | | | | | | |
| Spacing of Longitudinals | | Amidships | | | At Ends | | | | | | | | |
| Transverses. | | Depth and Thickness | | 15"-12"X10Lbs. ✓ | 15"-12"X10Lbs. ✓ | | | | | | | | |
| Side (in 'tween Decks) | | Face Angles | | 4"flange ✓ | 4"flange ✓ | | | | | | | | |
| | | Lugs to Shell* | | 3 3 4.89 | 3 3 4.89 | | | 3/4 | 3/8 | ✓ | | | |
| Side (in Hold) | | Depth and Thickness | | 15"X10Lbs. ✓ | 15"X10Lbs. ✓ | | | | | | | | |
| | | Face Angles | | 4"flange ✓ | 4"flange ✓ | | | | | | | | |
| | | Lugs to Shell* | | 3 3 4.89 | 3 3 4.89 | | | 3/4 | 3/8 | ✓ | | | |
| Bottom | | Depth and Thickness | | 24"X 10Lbs. ✓ | 24"X 10Lbs. ✓ | | | | | | | | |
| | | Face Angle | | Single 4 3 8.45 | 4 3 8.45 | | 4X2 1/2 X7.81Lbs. ✓ | | | | | | |
| | | Lugs to Shell* | | 3 3 4.89 | 3 3 4.89 | | | 3/4 | 3/8 | ✓ | | | |
| | | " " Back Bars | | | | | | | | | | | |
| Brackets | | 10Lbs. Bracket 4'-0" above base at side with 4"flange. ✓ | | | | | | | | | | | |
| Spacing of Transverse Frames | | 8'-0" ✓ | | | | | | | | | | | |
| | | All lugs intercostal between Longitudinal frames ✓ | | | | | | | | | | | |
| Longitudinal Beams of t, L-E | | Bridge Deck | | As Approved by Admiralty | | | | Spacing. | | | | | |
| | | Upper | B.A. | 6 | 3 1/2 | 10.7 | 6 | 3 1/2 | 10.7 | 6"X3"X11.37Lbs. B.A. | 24"-27" | | |
| | | Second | B.A. | 5 | 2 1/2 | 7.3 | 5 | 2 1/2 | 7.3 | 5"X3"X8.17Lbs. B.A. | 27" | | |
| | | Third | B.A. | 6 | 3 1/2 | 10.7 | 6 | 3 1/2 | 10.7 | 6"X3"X11.37Lbs. B.A. | 20 1/2"-27" | | |
| Transverse Beams. | | Centre | | 24"X10Lbs. 5X3 1/2 X15.01Lbs. Upper | | | | | | | | | |
| | | Side | | 12"X10Lbs. 4"flange (deck | | | | | | | | | |
| | | Centre | | 12"X10Lbs. 4"flange 2nd. | | | | | | | | | |
| | | Side | | 12"X10Lbs. 4"flange 3rd. | | | | | | | | | |
| | | Centre | | 15"X10Lbs. 4"flange (deck | | | | | | | | | |

The particulars of framing in peaks (if ordinary), Floors, Centre Girder, Side Girders and Margin Plate and their angle attachments, etc., to be entered in their respective places provided for on the Report Forms.

NOTE:—This slip to be pasted on the fourth page of the Report, and reference to same to be made under framing, etc., on the first page.