

S.S. "AOTEAROA".

H.M.S. "AVENGER".

Copy of notes taken by Mr. Minchin during the course of the repairs to the turbines.

MAGE Cause and date not given. The vessel on Admiralty Service.

UND. Starboard H.P. Turbine, 8 expansions of blading in Rotor and casing found damaged.

Starboard L.P. Turbine, Dummy on L.P. astern casing (lower half) found cracked in three places.

Starboard H.P. Turbine, 4 expansions of blading in Rotor and casing found damaged.

Port L.P. Turbine, Dummy on L.P. astern casing (lower half) found cracked.

IRS. All Turbines removed from vessel to shop.

Starboard H.P. 8 expansions of blading on Rotor and in casing renewed.

Starboard L.P. astern Dummy renewed by a forging secured to casing (lower half)

Port H.P. 4 expansions of blading on Rotor and in casing renewed.

Port L.P. astern Dummy renewed by forging secured to casing (lower half)

Turbines replaced on board and tried under steam and found satisfactory.

ING. Propeller and its fastings also sea connections fastenings examined and found satisfactory.



© 2018

Lloyd's Register
Foundation