

All communications to
be addressed to
THE SURVEYORS.



Lloyd's Register of Shipping.

HEAD OFFICE: 71, FENCHURCH STREET, LONDON, E.C. 3.

LLOYD'S REGISTER
RECEIVED
9-DEC-1935
Amst. 11
LONDON

Vienna ^{IV}/₂

Starhemberggasse 39/^{III}

7th December 1935

Curt Ross

Reference

Dear Sir,

We are in receipt of your letter of the 25th ult., with reference to the "Loeffler" boiler installation, and note with pleasure that the tests results are considered generally satisfactory.

Regarding the impact tests, the Izod test results, given in the certificate were read direct from the Izod testing machine, in metre kilograms, thus the results given are in metre kilograms and not metre kilograms per sq cm.

The special reason why the results of the Izod tests are so much lower than those of the Messnager tests, is due to the different shape of the notches, viz: pointed for Izod and round for Messnager tests.

It is also found, that material of high tensile strength, especially when it is welded, gives much larger differences between the Izod and Messnager tests.

We are, Dear Sir,

Yours faithfully,

The Secretary,

L o n d o n.



© 2018

Lloyd's Register
Foundation


Referred to the Chief Engineer, Zurich

252-827-947-24

THE SURVEYORS
All communications to
be addressed to

Lloyd's Register of Shipping

Head Office: 71, Fenchurch Street, London, E.C. 3.



Reference

Dear Sir,

We are in receipt of your letter of the 25th ult., with reference to the "Loeffler" boiler installation, and note with pleasure that the test results are considered generally satisfactory.

Regarding the impact tests, the Izod test results,

given in the certificate were read direct from the Izod testing machine, in metric kilograms, thus the results given are in metric kilograms and not metric kilograms per sq. cm.

The special reason why the results of the Izod tests are so much lower than those of the Messanger tests, is due to the different shape of the notches, viz: pointed for Izod and round for Messanger tests.

It is also found, that material of high tensile strength, especially when it is welded, gives much larger differences between the Izod and Messanger tests.

We are, Dear Sir,

Yours faithfully,

The Secretary,



© 2018

Lloyd's Register Foundation

Referred to the Chief Engineer Surveyor