

REPORT OF SURVEY FOR REPAIRS, &c.

Date of writing Report

When handed in at Local Office

Port of

LIVERPOOL

20 APR 1940

No. in Survey held at Liverpool
Reg. Book. 28255 on the Wood, Iron or Steel % s.s. "LANCASTRIA."Date, First Survey 10/4/40 Last Survey 5/5/40
(No. of Visits) 2 TRADETONNAGE— Built at Glasgow. By whom W. Beardmore & Co. When 1922-6
GROSS 16243. Owners Curved White Star Line Owners' Address
UNDER D.K. 12147. Managers Port belonging to Liverpool

Surveyed Afloat or in Dry Dock? Yes Name of Dock Glendale Destined Voyage

Cell DB or D.B.A. feet; u.E&B feet; f feet
total capacity tons. F.P.T. tons; A.P.T. tons; M.T. feet tonsParticulars of Classification (which must be inserted
preceding as in Register Book & Supplements)Only alterations in the existing records of tanks should be inserted.
N.B.—All alterations in the existing records should be underlined.

Last Report, No. 113928 Port Lw.

(Periodical Surveys, when held, must be reported in detail and variations in the terms of the Rules and items remaining to complete the Survey should be summarised. State clearly the cause of Repairs, if any, and, in detail, the nature and extent of Examinations and subsequent repairs. Repairs on account of Damage (the cause of which must be stated) should be separated from Repairs due to other causes; and besides being detailed in the body of the report, should be summarised in the form shown below. Whenever the replacement of Anchors or Chains is reported the particulars should be clearly stated in the space provided on the back of this form. State also the dates and initials of any letters respecting this case.)

In damage cases where the Surveyor has not made a special damage report he is required to state whether he offered his services for this purpose and to whom and why they were declined.

Yes not required Was a damage report made by anyone else? If so, by whom? *SEE SPL. NOTE S.R.L.*

REPAIRS, OR EXAMINATION AS PER RULE, FOR Damage stated to have been sustained

by encountering heavy weather on 15/3/40: See also S.R.L.

Vessel examined afloat, on Port side quarter found in way of crew quarter 1 shell plate - 7 frames in way slightly & set in & between knees started. tween deck bulkhead in way slightly buckled.
Now reinforced & made tight. & broken sidelights in way (c. dud) broken & small crack on deck had in way of main stairway on Port side now electrically welded & all in my opinion satisfactory.

S.R.L. Nothing has been done at this time to the items as per S.R.L.

SUMMARY OF DAMAGE REPAIRS:—	Shell Plates.	Frames.	R. Frames.	Floors and Bracket Floors	Beams.	Inner Bottom Plates.	Dk. Plates.	Other Items:—
Removed								
Removed and Fairied or Repaired								
Fairied or Repaired in place								

PRESENT CONDITION OF THE	Bulkheads	Ceilings	Engine Room Skylights	Copper, or Y.M. (State if on Board)
Decks as above & good	as above	✓	✓	/
Caulking of Decks do	do			
Coamings do				
Beams & Fastenings as above				
Outside Plating as above				
... in way of sidelights do				
Frames do				
Reverse Frames ✓				
Longitudinals ✓				
Transverses ✓				
Floors ✓				
Keelsons ✓				
Stringers ✓				
Inner Bottom Plating ✓				
Have the Tanks been examined internally? —				
Have the Tanks been tested? —				
	Doubling Plates under sounding Pipes ✓			
			(State if examined.)	

General Observations, Opinion as to Class, Recommendation, &c.:—

State clearly whether any and, if so, what alteration is suggested to be made in the existing classification and notification of the vessel in the Register Book consequent upon this survey, thus, for example:—"to remain as classed in the Register Book without fresh record of Survey," "to remain as classed and to have record of Survey, 1-35," or "to remain as classed and to have record of survey, 1-35, and the notations of as No. 1-35."

This vessel is in my opinion eligible to remain as now classed without fresh record of Survey, subject to the indicated listing frames &c being repaired at Owners convenience, & to internal examination of N.E. & S.E. D.P.T. & settling & storage tanks at first convenient opportunity. fram in way of E.S.D. when device removed & to repair, retest & replacement of 15 ft. cable.

Survey Fee (per Section 20)	£ 0 : 0 : 0	Fees applied for, 24 APR 1940
Special Damage (per Sec. 20)	£ 5 5 0	Received by me, 19
Travelling Expenses (if chargeable)	£ 0 : 0 : 0	
Second Surveyor's Fee (if any)	£ 0 : 0 : 0	

Committee's Minute LIVERPOOL 30 APR 1940

Character Assumed As now Subscr.
B.S. 1-40 QPH

Surveyor to Lloyd's Register of Shipping.