

# Lloyd's Register of Shipping.

## SURVEYS FOR FREEBOARD.

(COMPUTATION FOR STEAMER, SAILING SHIP, TANKER.)

Ship's Name <b>TRAUEWERFT LÜBECK</b>	Official Number	Nationality and Port of Registry	Gross Tonnage	Date of Build	Port of Survey <b>Hamburg</b>
Nos. 194 + 195					Date of Survey
Moulded Dimensions: Length <b>193.5</b> Breadth <b>32.5</b> Depth <b>20.284</b>					Surveyor's Signature
Moulded displacement at moulded draught = 85 per cent. of moulded depth					Particulars of Classification <b>100 A1 (proposed)</b>
Coefficient of fineness for use with Tables <b>.78 (assumed)</b>					

<b>DEPTH FOR FREEBOARD (D).</b> Moulded depth ... <b>20.28</b> Stringer plate <b>12.5 (assumed)</b> ... <b>.04</b> Sheathing on exposed deck $T \left( \frac{L-S}{L} \right) =$ <b>8</b> Depth for Freeboard (D) = <b>20.29</b>	<b>DEPTH CORRECTION.</b> (a) Where D is greater than Table depth $(D - \text{Table depth}) R =$ $(20.29 - 12.90) \times 1.489 = 11.00$ <b>7.394</b> (b) Where D is less than Table depth (if allowed) (Table depth - D) R = If restricted by superstructures	<b>ROUND OF BEAM CORRECTION.</b> Moulded Breadth (B) <b>32.5</b> Standard Round of Beam = $\frac{B \times 12}{50} = 7.8$ Ship's Round of Beam = <b>7.87 (200%)</b> Difference Restricted to Correction = $\frac{\text{Diff}^c}{4} \times \left( 1 - \frac{S_1}{L} \right) =$ <b>NIL</b>
--	---	---

## DEDUCTION FOR SUPERSTRUCTURES.

	Mean Covered Length (S)	Equivalent Enclosed Length (S <sub>1</sub> )	Height	Height Correction	Effective Length (E)	
Poop enclosed ...						Standard Height of Superstructure <b>6.0</b>
" overhang ...						" " R.Q.D. <b>-</b>
R.Q.D. enclosed ...						Deduction for complete superstructure <b>25.35</b>
" overhang ...						Percentage covered $\frac{S}{L} = 10.34$
Bridge enclosed ...						" $\frac{S_1}{L} = 10.34$
" overhang aft ...						" $\frac{E}{L} = 10.34$
" overhang forward ...						Percentage from Table, Line A.
Fore enclosed ...	<b>20.0</b>	<b>20.0</b>	<b>7.0</b>	<b>-</b>	<b>20.0</b>	(corrected for absence of forecastle (if required)) <b>5.17</b>
" overhang ...						Percentage from Table, Line B.
Trunk aft ...						(corrected for absence of forecastle (if required))
" forward ...						Interpolation for bridge less than 2L (if required)
Tonnage opening aft ...						Deduction = <b>25.35 + 5.17 = 30.52</b>
" " forward ...						
Total ...	<b>20.0</b>	<b>20.0</b>			<b>20.0</b>	

## SHEER CORRECTION.

Station	Standard Ordinate	S	M	Product	Actual Ordinate	Effective Ordinate	S	M	Product	
A.P. ...	<b>29.35</b>	1			<b>28</b>	<b>28.00</b>	1		<b>28.00</b>	Mean actual sheer aft = <b>less than I</b>
$\frac{1}{2}L$ from A.P. ...	<b>13.06</b>	4			<b>10</b>	<b>10.00</b>	4		<b>40.00</b>	Mean standard sheer aft
$\frac{2}{3}L$ " ...	<b>3.23</b>	2			<b>1</b>	<b>1.00</b>	2		<b>2.00</b>	Mean actual sheer forward = <b>less than I</b>
Amidships ...	<b>0</b>	4			<b>0</b>	<b>0</b>	4		<b>0</b>	Mean standard sheer forward
$\frac{2}{3}L$ from F.P. ...	<b>6.46</b>	2			<b>11</b>	<b>11.00</b>	2		<b>22.00</b>	Length of enclosed superstructure forward of amidships =
$\frac{1}{2}L$ " ...	<b>26.12</b>	4			<b>36</b>	<b>36.00</b>	4		<b>144.00</b>	" aft of " =
F.P. ...	<b>58.70</b>	1			<b>57.0</b>	<b>57.00</b>	1		<b>57.00</b>	
Total ...				<b>264.15</b>		<b>62.00</b>			<b>618.00</b>	

Correction =  $\frac{\text{Difference between sums of products}}{18} \left( \frac{.75 - S}{2L} \right) =$   
 If limited on account of midship superstructure. **10 Deduction on account of midship**

If limited to maximum allowance of  $1\frac{1}{2}$  ins. per 100 ft.

## Deduction for Tropical Freeboard.

## Addition for Winter and Winter North Atlantic Freeboard.

Depth to Freeboard Deck = **20.29**  
 Summer freeboard = **2.35**  
 Moulded draught (d) = **17.94**

Deduction for Tropical freeboard and addition for

Winter freeboard =  $\frac{d}{4}$  inches =

Addition for Winter North Atlantic Freeboard (if required) =

## Deduction for Fresh Water.

Displacement in salt water at summer load water line  
 $\Delta =$   
 Tons per inch immersion at summer load water line

Deduction =  $\frac{\Delta}{40 T}$  inches

## TABULAR FREEBOARD corrected for Flush Deck (if required)

Correction for coefficient

Depth Correction ... **11.00**  
 Deduction for superstructures ... **1.31**  
 Sheer correction ... **1.94**  
 Round of Beam correction ... **1.02**  
 Correction for Thickness of Deck amidships ...  
 Other corrections, scantlings, etc. ... **10.99**

Summer Freeboard = **34.23**

## SUMMER FREEBOARD amidships from Centre of Disc to top of Deck Line, Wood, Steel, Deck :-

Tropical Fresh Water Line above Centre of Disc	...	Tropical Fresh Water Freeboard	...
Fresh Water Line	"	Fresh Water	"
Tropical Line	"	Tropical	"
Winter Line below	"	Winter	"
Winter North Atlantic Line	"	Winter North Atlantic	"

© 2020

Lloyd's Register  
Foundation



A new form should be prepared if any alterations that affect the freeboard have been made. If no such alterations have been made, the Surveyor should endorse the form on this side with his signature and the date.

At 17'-5" moulded draught.

$$LBP = 192.25 \checkmark$$

$$LWL = 201.75 \times .96 = 193.5 \text{ approx.} \checkmark$$

22'-10"	24 + 4	28
21'-8"	10 -	10
20'-11	1 -	1
② 20'-10	—	
21'-9	11 -	11
23'-9	35 + 1	36
25'-5	55 + 7	62

Standard

$$29.35 \times 1$$

$$16.29 \times 3$$

$$29.35$$

$$48.87$$


---


$$78.22$$

Actual.

$$28.00 \quad 1$$

$$18.00 \quad 3$$

$$28.00$$

$$33.00$$


---


$$61.00$$

$$\frac{61.00}{78.22} = 78\%$$

Trade of ship \_\_\_\_\_

Names of sister ships \_\_\_\_\_

Builder's name and yard number \_\_\_\_\_

Owners \_\_\_\_\_

Fee £ \_\_\_\_\_



© 2020

Lloyd's Register  
Foundation