



**EQUIPMENT**

3 BOWER ANCHORS STOCKLESS	A	3795 KG.
1 STREAM		1210 "
495 METRE 58.5% (2 3/4) STUD SHAW CABLE (2% LOWER REQ)		
165 "	127 3/4 (5")	STEEL WIRE (6-16)
220 "	121 3/4 (4 1/2)	(6-24)
2.165 "	70 3/4 (2 3/4)	
2.165 "	64 3/4 (2 1/2)	

**DIMENSIONS**

LENGTH P.P.	418'-0" = 127.43 MET.
BREADTH MOULDED	56'-6" = 17.22 "
DEPTH TO UPPER DECK	38'-0" = 11.582 "
D LLOYDS	37'-3" = 11.354 "
L x D	15571 FEET = 1447 "
L x (B-D)	39188 " = 3640 "
L x D	110 "
EN.	60232 FEET = 3738 "

ALL BULWARKS NEW GERMAN STANDARD 1927  
BUTTS WELDED IN SHELL, DECKS, AND TANKTOP

CLASS: LLOYDS REGISTER + 100A1, WITH FREEBOARD FOR A DRAUGHT CORRESPONDING TO A COMPLETE SUPERSTRUCTURE VESSEL HAVING A TONNAGE OPENING: BUTTS OF SHELL AND DECKS ELECTRICALLY WELDED

OWNERS' REQUIREMENT

**RETAIN**

44000 5800/595  
GOTHENBURG FIRST ENTRY REPORT No. 13474

m/s Akkav

**AKTIEBOLAGET GÖTAVERKEN**

M/5568	AKKAV	BEST FOR	BEST NE
MIDSHIP-SECTION			
3000 TONS ORE CARRIER			
(to filled)			
RITAV	AKKAV	AKKAV	AKKAV
KALKERAV	AKKAV	AKKAV	AKKAV
GRANSKAV	AKKAV	AKKAV	AKKAV

2

2646

CORRECTED AS BUILT 1-9-62  
CORRECTED AS APPROVED BY LLOYD'S REGISTER 3-10-60