

Proposed New "Moyallon"

Depth increased to 10'-0"

23.12.26

By phone to Ailsa today: [Mr. Adam]


If whole ship raised 3", increase in draught about 3"

If upper deck alone raised, R.Q.D. as before kept at original height, increase in draught about 2"

Frame in way of R.Q.D. (if raised) should be 6x3x.32 as actually used in Moyallon

Frame in way of Upper Deck should be increased .04 or beam knees made 3" deeper.

Equipment the same as Moyallon.



© 2020

Lloyd's Register
Foundation

002013-062023-0113