

## LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

18 APR 1955

## ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name "CITRINE" Official No. 165956

Port of Registry Glasgow

This ship has been under survey at Brangemonth

on 22/3/1955. and the following alterations to the conditions of

assignment of loadlines have now been effected/found:—

Companion aft end of poop deck to steering gear compartment removed opening in deck plated over.

Ladderway enclosed in house aft end poop deck (ps) plated over.

W.T. escape hatch (ps) above casing on poop deck removed openings plated over.

Access door to Engine Room on Poop Deck (ss) plated over.

Ladderway enclosed in house at forward end of poop deck (ss) plated over.

1-16" dia. Escape light fitted on poop front (ps) Deadlight fitted.

Additional Ventilators etc:—

Poop Deck: 2-8" dia. Coal Ventilators. 30" high x 32. Wood plug + canvas cover supplied.

4-5" G.N. Ventilators. 30" high.

1-3" dia. air pipe 30" high

Casing 2/p: 1-6" dia. Coal Ventilator. 30" high x 32. Wood plug + canvas cover supplied.

3-5" G.N. Ventilators 30" high.

2-3 1/2" dia. air pipes 30" high. Fitted with gauges + canvas covers.

James Fleming  
Glasgow

22/3/55.

Noted  
am  
19.4.55

A copy of this Report has been placed on board.



© 2020

Lloyd's Register

002038-002050-0066



# PARTICULARS OF PROTECTION TO OPENINGS, ETC.

HATCHWAYS ON FREEBOARD AND SUPERSTRUCTURE DECKS.									
Description of Hatchway		fore all		K. Q. cleat					
Dimensions of Hatchway		34'-10" x 19'-6"		62'-4" x 19'-6"					
COAMINGS	Height above Deck	3'-3 3/4"		3'-5 3/4"					
	Thickness	.44		.44					
	Stiffeners	8 x 3 x .44		8 x 3 x .44					
	Brackets, Stays	12 x .56		12 x .56					
HATCH BEAMS	Number	5		11					
	Spacing	17 3/4" x .36"		15" x .36"					
	Scantling and Sketch	4 x 3 x .44		4 x 3 x .44					
	Bearing Surface	4		4					
FORE AND AFTERS	Number								
	Spacing								
	Unsupported Lengths								
	Scantling* and Sketch								
HATCH COVERS	Material	pine		pine					
	Thickness	2 1/2"		2 1/2"					
	How fitted	longitudinally		longitudinally					
	Bearing Surface	4"		4"					
Spacing of Cleats		24"		24"					
Number of Tarpaulins		2		2					
<p>*Are wood fore and afters steel shod at all bearing surfaces? <input checked="" type="checkbox"/></p> <p>Are battens and wedges efficient and in good condition? <input checked="" type="checkbox"/></p> <p>Are tarpaulins in good condition and in accordance with rule requirements? <input checked="" type="checkbox"/></p> <p>Are lashings provided in accordance with rule requirements? <input checked="" type="checkbox"/></p> <p style="color: red;">Special Lashings fitted to this Hatchway.</p>									

Particulars of any special features:—

Hatch A. 2'-8" x 2'-8" height 2 feet x .28 2 1/2" wood cross cleats 24" apart  
Hatch B. 2'-6" x 2'-2" height 2 feet x .28 2 1/2" wood cross cleats 24" apart  
2 Tarpaulins for each hatch.

Displacement 10'-6" ————— 1188 M<sup>3</sup> } tons per inch 10.5  
Displacement 11'-6" = 85% maximum depth 1318 M<sup>3</sup> } tons per inch 11.08  
Displacement 12'-6" ————— 1451 M<sup>3</sup>

Endorsement at first survey and at surveys for renewal of Certificate:—

The fittings and appliances are in accordance with the particulars shown on this form (or as now modified) and are in good condition.



© 2020

Lloyd's Register Foundation