

(NORTH SANDS LIBERTY)

TO "FORT TADOUSSAC"
(FIRST OF THIS TYPE)

DARFIELD

Victoria Machinery Depot Co. Ltd., Victoria B.C.

Yard No. 28.

Sister vessel to the "FORT ST. JAMES". ? FORT LIARD/FORT STURGEON

5c.7.42

? FORT CAMOSUN ETC.

F.E.
(FBD)The scantlings are suitable for a draught of $18\frac{1}{2}$ " in excess of that corresponding to the freeboard which could be assigned as a C.S.S. vessel.

Received by Chief Ship Surveyor.....

Received from Chief Ship Surveyor.....

VESSEL'S NAME s.s. "YOHO PARK" REPORT Ver. No. 5935

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

D to W dk 37.33' D to 2nd dk 28.58' D for scantlings 36.58' (i.e. 8' above 2nd dk).

1st Long No. 15217

Depth "d" -

2nd Long No. 38879

Proportions = $\frac{L}{D}$ 11.14

Framing As approved

Sheerstrake As approved

The equipment of chain cables is deficient by 90 fathoms, which was agreed to as per Special Endorsement 5.3.43.

SEE SPECIAL CORRESPONDENCE ETC. RE ANCHORS.

Slight contact damage to E & F strakes of shell plating etc. in way of holds Nos. 2 & 3 (p.s.) has been dealt with.

This vessel appears to have been built in accordance with the

Rules and the approved plans, and it is submitted she is eligible to

be classed *100A1 "With freeboard", subject to 45 fathoms of chain cable being supplied at the earliest opportunity.

The Summer Freeboard as shown on the attached extract from the

Freeboard Verification Form, now marked on the vessel's sides, to be

inserted in the classification certificate and recorded in the Register

Book, and further, the remaining freeboards, as shown on the accompanying

extract, to be inserted in the certificate of classification.

2 Dks "Butts of shell and deck plating electrically welded".

Cell DB 368' 1149t, DTA 20' 765t, FPT 145t, APT 160t

FK, 7BH (Coll to W dk, 6 to 2nd dk) 6 divisional W.T. BHs in 'tween dks., pt.Cem.

O.L. 441.5'

E.S.D.

a

The class is assigned and maintained upon the understanding that the equipment will be made to accord with the requirements of the Rules and the two bower anchors and stream anchor on board submitted to the Statutory Test when the present state of emergency has passed

Insert also in S.R.L:- (A bower anchor and 45 fathoms of chain cable to be supplied and two bower anchors and stream anchor on board to be submitted to Statutory Test).

NOTE: See correspondence attached to First Entry on "FORT ST. JAMES" re scantlings.

002038-002050-0177

13.9.43