

FREEBOARD REPORT on the S. S. KYANITE.

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval, *subject to.*

- ① The hatch covers of the main hatchways being ~~repaired~~ made good ~~sufficient~~ to the surveyors satisfaction.
- ② The hatch webs of the main hatchways being made good & reasonably to comply with the Convention requirements.
- ③ All air pipes being provided with satisfactory closing appliances.
- ④ The freeing port area in the raised quarter deck bulwarks being increased to 19'4 sq. ft each side.

The Glasgow surveyors should be informed that it is noted the thickness of the hatch webs of no 2 hatchway is reported as .14 & that the thickness of the angle mountings is very much below rule. These webs should be made good to the surveyors satisfaction & reasonably to comply with the Convention requirements. (B.B.)

Asst. Dir.
Convention Bureau
24.6.32

002062-002070-0165

Lloyd's Register
Foundation