

## FREEBOARD REPORT on the

Kathleen.

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval, subject to:-

- 1) Bearing surfaces of covers of Aft Peak Store and Lining Hatchways being increased to Convention requirements.
- 2) Wood fore-and-afters of Cargo Hatchways being steel shod at all bearing surfaces.
- 3) Efficient means being provided for securing door of companionway to crew space aft.
- 4) Efficient means of closing being provided for all airpipes and for ventilators not already supplied with same.
- 5) Guard rails on Forecastle being repaired or renewed where necessary to Surveyor's satisfaction.
- 6) Suitable provision being made for rigging lifelines, which should be available for use in any part of the ship which might have to be used by the crew in the regular working of the ship.
- 7) Freeing port area of Raised Quarter Deck Bulwark being increased to  $20\frac{1}{2}$  sq. feet on each side of ship.
- 8) Locks of door in companionway below main deck, and cleats in trimming hatch on foreboard deck under foremast being repaired to Surveyor's satisfaction.

Convention

Approved  
14/9/32

J. M. M.

© 2020

Lloyd's Register  
Foundation

R. G. K.

13-9-32