

25 JAN 1947

Index No.

Lloyd's Register of Shipping.

Ship's Name

HAI HU ex Ottawa Pawler

Official No.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in

Alterations: Forecastle Head

Steel casing with hinged steel door operated from both sides fitted at the
after end of the Forecastle Head and forecastle fitted out for crews
accommodation.

Steel Casing $\frac{1}{4}$ " thick, 3 x 3 x $\frac{1}{4}$ " stiffeners spaced 2'6" apart secured to
ground and deck head bars.


Steel Door $\frac{1}{4}$ " thick opening 5'6" x 24" sill 14".

Portlights 2 - 10" C.I. hinged portlights with hinged deadlights fitted
port & starboard.

Native W.C. 2 bowls fitted, port aft, outside of accommodation. Steel
casing not yet fitted.

3" soil pipe lead to 3" C.I. storm valve fitted below main deck,
adequately protected.

Brass storm valve to be fitted on vessel's return to Shanghai
in lieu of C.I. valve.



© 2020

Lloyd's Register
Foundation

002071-002078-0171