

Burrard Dry Dock Company, Limited, Vancouver B.C.Yard No.245.**F.E.**
(FBD.)"B" Type Coaster & sister vessel to "OTTAWA PANDA" etc.

Received by Chief Ship Surveyor.....

Received from Chief Ship Surveyor.....

VESSEL'S NAME s.s. "OTTAWA PALMER" REPORT Ver. No. 6830

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

1st Long. No. 4532

Depth "d" -

2nd Long. No. 12197

Proportions = $\frac{L}{D}$ 9.7

Framing Bulb angle framing as approved Sheerstrake As approved

This is a complete superstructure vessel with tonnage opening and the scantlings are in accordance with the Rule requirements for this type.

The tank top plating has been increased .06" in thickness in lieu of ceiling under the hatchways.

This vessel appears to have been built in accordance with the Rules and the approved plans, and it is submitted she is eligible to be classed ~~8100A1~~ "With freeboard" "Fitted for oil fuel 3.46, FP above 150°F".
3.46 Vcr.

The Summer Freeboard as shown on the attached extract from the Freeboard Verification Form, now marked on the vessel's sides, to be inserted in the classification certificate and recorded in the Register Book, and further, the remaining freeboards, as shown on the accompanying extract, to be inserted in the certificate of classification.

1 Dk & Shelter dk "Part elec. welded"
Cell DB 144' 260t, DTf 6' 77t, EPT 37, APT 24t
FK, 4BH (Coll to Sh dk, 3 to 2nd dk) Lloyd's A & CP
F 30'
Mchy Aft
O.L. 224.2'
Extreme breadth over belting: 37.9'
"n"



W.O.T. f.c.d.
6.6.46. 2020 ✓

Lloyd's Register
Foundation

002071-002078-0176