

Lloyd's Register of Shipping.

Ship's Name

ASCANIA

Official No.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in ALTERATIONS.

Vessel's Accommodation altered at this time from Trooping to Passenger Status.

① The following Hatches additionally trunked:—

102	between "E" & "B" Decks	Hatch Beland & Covers fitted at "B" Deck level And it was arranged with the Owners that these Hatches would carry cargo at <u>not</u> more than 100 cu ft per ton from "B" Deck level to "A" Deck level only (Two Tonnage Decks).
103	" " "	
106	" " "	
107	" " "	

② Existing Transit Lunge frame 40-48 increased to frames 39-48 and extended outboard from 20'-0" from Centre line to Ship's Side per.

③ Additional Storm Values: All geared to Freeboard Deck.

1	@ 2½" Diam Bath & Basin Discharge	Frames 153-4 Port
1	@ 2" " Scupper	" " " " Starboard
1	@ 4" " Scub	" " 150-1 "
1	@ 4" " "	" " 127-8 Port & Starboard.
1	@ 3" " Bath & Scupper	" " 127-8 "
1	@ 3" " Sewage Tank	" " 100-1 Starboard.
1	@ 5" " Scub	" " 24-5 "

Scub on Port Side deleted.

1 @ 3" Diam Sewage Tank Discharge Frame 7-8 Starboard.

The above Dischargers are from "E" Deck level. (Deck below freeboard deck)

④ 10 New Steam Tank Supply Units installed in Accommodation with Natural Exhaust through Roofs.

A copy of this report put on board vessel

John Stantford
Clerk.

12th April 1950