

Moulded Depth

Raised Quarter Deck

3

6

1 1/2

002085-002093-0195

5m.5.32.

FREEBOARD REPORT on the S.S. EVELEEN

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval. subject to:-

1. One additional tarpaulin being supplied to each of the cargo hatchways.
2. Efficient means being provided for closing the openings of all the ventilators, also for closing the openings of the air pipes
3. The fiddle gratings being fitted with efficient steel covers permanently attached, if this is not already the case.
4. Suitable provision being made for rigging lifelines which should be available for use in any part of the ship which might have to be used by the crew in the regular working of the ship.
- 4A. The freeing port area in the Raised Quarter Deck bulwarks being increased to 19 sqft. each side.
5. The steel door in the machinery casing on the Raised Quarter Deck being made capable of being closed and secured from both sides.
6. The Hatch cover rest bar on the Hunter Hatchway, the engine room ventilator coaming and the lock of the steel door of the Trunkway on freeboard deck leading to the fore peak store being repaired to the satisfaction of the Surveyor.
7. The main cargo hatch covers being made equivalent to the Convention requirements, particulars of the Convention alterations being forwarded to this Office.

Draught for record

12

1 1/2