

## Lloyd's Register of Shipping.

Ship's Name

S.S. "AVON COAST"

Official No.

147391

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

1. The freeing ports in the tonnage well have been permanently plated over.
2. Overboard scuppers draining the freeboard deck have been permanently closed except in tonnage well where a 5" diam. scupper, with non-return valve operated from the superstructure deck has been provided (p.s.) means of showing when valve is open or closed has been provided.
3. Two scuppers have been fitted (p.s.) to drain freeboard deck to machinery space bilges. These are fitted with weighted lever cocks at their lower ends.

Kenneth Murray  
Lloyd's Register of Shipping  
Liverpool  
12th June 1946.