

Lloyd's Register of Shipping.

Ship's Name S.S. "URBINO".Official No. 139343

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in _____

The following alterations have now been examined and found satisfactory:-

In way of saloon pantry:- Access hatchway cut in bridge deck plating for access to storeroom in tween deck spaces. Hatchway 3 ft. x 3 ft, with 3 x 3 x 3/8" angle coaming, efficiently closed by hinged steel cover secured by padlock.

In way of new crews' accommodation in poop space:- An efficient steel deckhouse fitted on C.L. of poop deck, enclosing two companionways to P. & S. poop spaces. House 21 ft. by 4'3" by 7 ft. 3" in height, with two hinged steel doors fitted with spring locks operated from both sides. Sill 15" high. 7 P. & 7 St. - 9" dia. ventilators fitted on poop deck, leading to crew spaces in poop. Coamings & closing appliances to rule requirements.

1 P and 1 St. - 12" dia. ventilators fitted on poop deck, leading to crew spaces in poop. Coamings and closing appliances to rule requirements.

No.6 hatchway on poop now trunked through the poop spaces into the lower hold. After 2ft. of poop deck hatch coaming blanked off by new trunking and adapted for ventilation duct for new accommodation; top of hatch coaming in way closed by E.W. steel plates, carrying two 16" dia. extractor fans.

AMB Edwards

SURVEYOR TO LLOYD'S REGISTER
OF SHIPPING.

17.5.49.

