

11 JUL 1950

56667

Rpt. C. 11 (Contd.)

Index No. 21086

Lloyd's Register of Shipping.

Ship's Name

"YOKEFLEET".

Official No. 129515

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

The following alterations carried out at this time:-

No.2 hatchway lengthened two frame spaces further aft (3'-8").
 Additional hatchway beam fitted 32½" at centre, 30" at ends, .38" thick with 2½" x 2½" x .30" double top mounting angles and 3" x 1½" double half rounds at bottom.
 Hatch covers, tarpaulins and battening arrangements altered to suit new length of hatchway.

Bunker hatchway forward coaming moved 1 frame space aft and extended to full height of machinery casing (6'-6"). 9" B.A. coaming fitted in casing top with cleats, hatchway tarpaulins and battening arrangements to Rule Requirements.

Existing door in casing side (s.s.) permanently closed by E.W. and new hinged steel door fitted further forward, door sill 18" and door with spring locks operated both sides.

E. Howey


SURVEYOR TO LLOYD'S REGISTER OF SHIPPING.

6.8.50.

Noted.
AA

112 JUL 1950

ORIGINAL PLACED ON BOARD.



© 2020

Lloyd's Register Foundation