

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

2 - OCT 1954

ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name 'LADY DOROTHY' Official No. 137808.Port of Registry GLASGOW.This ship has been under survey at BOWLING.on 15th - 29th SEPTEMBER 1954. and the following alterations to the conditions ofassignment of loadlines have now been effected/~~found~~:FLOODING ARRGS.Existing flooding valves removed.New flooding valves fitted at this time in fwd. & after holds.Valves of gunmetal, screw down type.6" double valves fitted to steel inlet boxes at ship's side, fwd. hold (S.S. fwd.) and after hold (S.S. fwd.) with outlet pipes led to respectivespaces. Each valve controlled from freeboard ^{or raised quarter} deck with handwheelfitted with OPEN/SHUT indicator. Handwheels contained in steel ^{red painted} boxesseaming having steel cover plate secured with hasp and padlockKeys for same are in the possession of the master.J.R. Wilson.29/9/54.liblf

26 OCT 1954

A copy of this Report has been placed on board.