


"Lady Cornaught"

It is submitted the Dublin Surveyor be advised that the springs in the bridge fore bulkhead ~~at~~ on frame N. 37 are covered by Class 1 Closing appliances (Hardline Rules, Rule N. 50) and bulkhead is fitted at ~~the~~ frame N. 40, i.e. 10 feet forward of the fore end of the bridge, any springs therein being closed by Class 2 Closing appliances (Hardline Rules, Rule N. 51), a forebrain corresponding to a summer extreme draught of $16'2\frac{1}{4}"$ could be assigned

S.E.B.

13.7.42



© 2020

A.R.

Lloyd's Register
Foundation

002151-002156-0208

forward of amidships =

forward of amidships =