


Particulars for Freeboard  
S.S. 482'-0" x 54'-0" x 35'-10"



Length on waterline 481.5 feet ✓  
 Breadth extreme 54.4 ✓  
 Depth of Hold 31.84 ✓  
 " moulded 35'-4" ✓

35'-4" <sup>9</sup>/<sub>16</sub> inch  
 36'-1" <sup>3</sup>/<sub>16</sub> inch  
 32'-1 1/2" at midships length


Tonnage under upper deck about 6980 ✓

Sheer at stem 9'-6" ✓  
 " " 1/8 from stem 5'-3" ✓  
 " " 1/8 from post 1'-3" ✓  
 " " post 3'-6" ✓

Round of Beam 9" ✓  
 Rise in sheer amidships 3" ✓

Erections Poop 46'-6" ✓  
 Bridge enclosed 197'-6" ✓  
 " open one side 65'-0" ✓  
 Forecastle 44'-6" ✓

The above particulars to be verified from  
 Board of Trade measurements and  
 from the vessel.



Lloyd's Register  
 Foundation

002157-002164-0032

FRESH WATER LINE

ABOVE CENTRE OF DISC

Indian Summer Line

Amended Tables