

Lloyd's Register of Shipping.

Ship's Name

'LESTO'

Official No. 140710

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in

Additional Ventilators and Escape Hatch fitted to No 1 Hold & Cofferdam to fulfil requirements for carriage of Case Oil in No 1 Hold. Blyth 24/5/43.
2-6" dia Vents (1P+15) fitted in fore well Dk into Wood Cofferdam space at after end of No 1 Hold. Height coamings = height of No 1 hatch coamings made of substantial thickness and fitted with double gauge.

1-12" dia Vent x 25" fitted on raised coach deck before end of No 1 Hold Star Side
1-12" dia Vent x 25" fitted on raised coach deck before end of No 2 Hold Port Side
height of coamings = height of No 1 hatch coaming. Both fitted with double gauge.

Escape hatch 18" x 18" x 25" fitted with hinged WT steel lid, capable of being operated from both sides, fitted on raised coach deck into cofferdam space at after end of No 1 Hold. Height coaming = height of No 1 Hatch coaming.

Copy of above memo placed on board.

Jr

John T. M. J. J.

Noted S.W.B.

2 JUN 1943