

MIDSHIP SECTION

DIMENSIONS 170'-0" B.P. x 29'-0" EXT x 13'-6" MED TO MAIN DECK

SCALE $\frac{1}{2}$ " 1 FOOT

-TO CLASS 100 A.I.LLOYDS

LONGITUDINAL NUMBER		7199
RAISED QUARTER DECK	45.85×3.75	360
BRIDGE DECK	$14.66 \times 7.0 \times \frac{3}{4}$	77
FORECASTLE	$24.66 \times 6.75 \times \frac{3}{4}$	125
CASING	$42.16 \times 6.6 \times \frac{1}{2}$	139
EQUIPMENT NO =		7900

EQUIPMENT.

2	BOWER	ANCHORS	EACH	1 1/2	CWTS,	STOCKLESS
1	"	ANCHOR		12 3/4	"	"
1	STREAM	"		1 1/4	"	EX STOCK
1	KEDGE	"		2	"	"
195	FATHOMS	1 1/2	STUD	LINK	CHAIN	CABLE
60	"	3	STEEL	WIRE	IN LIEU	OF STREAM CHAIN
75	"	2 3/4	"	"	"	TOWNLIN.
90	"	6	"	"	"	HANSER.



